

Fall 2014

# Strategies For The Replacement Of Historic Bridge Guardrails

Adam J. Clauss  
*Purdue University*

Follow this and additional works at: [https://docs.lib.purdue.edu/open\\_access\\_theses](https://docs.lib.purdue.edu/open_access_theses)



Part of the [Civil Engineering Commons](#)

---

## Recommended Citation

Clauss, Adam J., "Strategies For The Replacement Of Historic Bridge Guardrails" (2014). *Open Access Theses*. 313.  
[https://docs.lib.purdue.edu/open\\_access\\_theses/313](https://docs.lib.purdue.edu/open_access_theses/313)

This document has been made available through Purdue e-Pubs, a service of the Purdue University Libraries. Please contact [epubs@purdue.edu](mailto:epubs@purdue.edu) for additional information.

**PURDUE UNIVERSITY**  
**GRADUATE SCHOOL**  
**Thesis/Dissertation Acceptance**

This is to certify that the thesis/dissertation prepared

By Adam J. Clauss

Entitled

STRATEGIES FOR THE REPLACEMENT OF HISTORIC BRIDGE GUARDRAILS

For the degree of Master of Science in Civil Engineering

Is approved by the final examining committee:

Robert Frosch

Mark Bowman

Michael Kreger

To the best of my knowledge and as understood by the student in the Thesis/Dissertation Agreement, Publication Delay, and Certification/Disclaimer (Graduate School Form 32), this thesis/dissertation adheres to the provisions of Purdue University's "Policy on Integrity in Research" and the use of copyrighted material.

Robert Frosch

Approved by Major Professor(s): \_\_\_\_\_

Approved by: Dulcy Abraham

12/01/2014

Head of the Department Graduate Program

Date

# STRATEGIES FOR THE REPLACEMENT OF HISTORIC BRIDGE GUARDRAILS

A Thesis

Submitted to the Faculty

of

Purdue University

by

Adam J. Clauss

In Partial Fulfillment of the

Requirements for the Degree

of

Master of Science in Civil Engineering

December 2014

Purdue University

West Lafayette, Indiana

I dedicate this thesis to my parents, Mark and Barbara Clauss. They provided me the opportunity to obtain *two* degrees from Purdue University. I will pay it forward.



## **ACKNOWLEDGEMENTS**

The author would like to thank Professor Robert Frosch of Purdue University and Professor Michael Kreger of the University of Alabama for giving him the opportunity to conduct this research. The author would also like to thank Professor Mark Bowman of Purdue University; George Snyder, Elizabeth Phillips, Greg Carleton, Tim Wells, Anne Rearick, and Mary Kennedy of the Indiana Department of Transportation; and Gregg Freeby and John Holt of the Texas Department of Transportation for their assistance and valuable input.

## TABLE OF CONTENTS

	Page
LIST OF TABLES .....	vi
LIST OF FIGURES .....	vii
ABSTRACT .....	x
CHAPTER 1. INTRODUCTION .....	1
1.1 Background .....	1
1.2 Objective and Scope .....	2
CHAPTER 2. REVIEW OF HISTORIC BRIDGE RAILING PRACTICE .....	3
2.1 History of Railing Design Standards .....	3
2.2 Current Railing Design Standards .....	4
2.3 Historic Bridge Identification .....	6
2.4 National Historic Bridge Management .....	7
2.5 Bridge Railing Manual .....	10
2.6 Historic Bridge Railing Research .....	11
2.7 Historic Replacement Railings .....	17
2.8 Modern Aesthetic Railings .....	19
2.9 Railing Approval .....	21
CHAPTER 3. DOCUMENTATION OF HISTORIC BRIDGES AND RAILINGS IN INDIANA .....	22
3.1 Indiana Historic Bridge Database .....	22
3.2 Analysis of the Historic Bridge Database .....	22

	Page
CHAPTER 4. BRIDGE RAILING RETROFIT STRATEGIES .....	34
4.1 Introduction.....	34
4.2 Bridge Railing Design Parameters.....	35
4.2.1 Required Test Level .....	36
4.2.2 Presence/Absence of a Sidewalk.....	37
4.2.3 Horizontal Roadway Clearance on a Bridge .....	38
4.3 Inboard Retrofit.....	39
4.4 Curb Retrofit .....	40
4.5 Railing Replacement.....	41
4.5.1 Reinforced Concrete Railings .....	45
4.5.1.1 TxDOT T221 Railing.....	46
4.5.1.2 ODOT Concrete Beam and Post Railing.....	53
4.5.2 Metal Tube Railings .....	55
4.5.3 Pedestrian Railings.....	60
4.5.4 Summary of Design Methodology .....	62
4.6 Retrofit Selection Procedure .....	63
CHAPTER 5. SUMMARY AND CONCLUSION .....	65
5.1 Summary .....	65
5.2 Conclusions.....	66
REFERENCES.....	68
APPENDIX A. MODERN RAILING STANDARD DRAWINGS.....	71
APPENDIX B. HISTORIC BRIDGES REMOVED FROM SERVICE UNDER INDIANA’S PROGRAMMATIC AGREEMENT.....	101
APPENDIX C. PHOTOS OF HISTORIC BRIDGE RAILINGS .....	103
APPENDIX D. SIMULATED HISTORIC RAILING RENDERINGS.....	124
APPENDIX E. SIMULATED HISTORIC RAILING DRAWINGS.....	167
VITA.....	228

## LIST OF TABLES

Table	Page
Table 2.1 – Changes from NCHRP Report 350 to AASHTO MASH.....	5
Table 2.2 – Summary of railing height requirements .....	6
Table 2.3 – TxDOT standardized historic approximation railings .....	17
Table 3.1 – In-Service Historic Bridges by Structure Type.....	24
Table 3.2 – In-Service Historic Bridges by Facility Carried .....	25
Table 3.3 – In-Service Historic Bridges by Facility Crossed .....	25
Table 3.4 – Railing types .....	26
Table 3.5 – Historic bridges by railing type .....	29
Table 3.6 – Summary of railing types observed on 5% or more of bridges .....	31
Table 4.1 – Historic railing approximation methods .....	42
Table 4.2 – Historic railings and approximating Custom Rock formliners .....	51
Table A.1 – List of standard drawings provided.....	71
Table B.1 – Historic bridges removed from service .....	101

## LIST OF FIGURES

Figure	Page
Figure 2.1 – States’ historic bridge management activities .....	8
Figure 2.2 – Roy B. Inks Bridge .....	12
Figure 2.3 – U.S. 281 Bridge .....	12
Figure 2.4 – Typical railing connection to truss member on the Roy B. Inks Bridge .....	13
Figure 2.5 – Test setup of the Roy B. Inks railing before crash testing.....	14
Figure 2.6 – Test setup of the Roy B. Inks railing after crash testing .....	14
Figure 2.7 – Roy B. Inks bridge with the retrofit railing developed at TTL.....	15
Figure 2.8 – Test setup of the U.S. 281 railing before crash testing.....	16
Figure 2.9 – Test setup of the U.S. 281 railing after crash testing.....	16
Figure 2.10 – TxDOT approximation of historic bridge railings.....	17
Figure 2.11 – INDOT TX railing profile .....	18
Figure 2.12 – INDOT TX railing installation .....	18
Figure 2.13 – Concrete railing with tribal design architectural texture .....	19
Figure 2.14 – Concrete railing with tribal design architectural texture .....	20
Figure 2.15 – Concrete railing with architectural treatment .....	20
Figure 2.16 – Concrete railing with architectural treatment .....	21
Figure 3.1 – Metal 6 railing (Rank 1) .....	32

Figure	Page
Figure 3.2 – Metal 5 (Galvanized Beam) railing (Rank 2) .....	32
Figure 3.3 – Concrete 1 (Bush-Hammered Panel) railing (Rank 3) .....	32
Figure 3.4 – Timber 1 railing (Rank 4) .....	32
Figure 3.5 – Concrete 2 railing (Rank 5) .....	33
Figure 3.6 – Concrete 6 railing (Rank 6) .....	33
Figure 3.7 – Metal 10 railing (Rank 7) .....	33
Figure 3.8 – Bridges with no railing (Rank 8) .....	33
Figure 4.1 – Typical barrier curb on a bridge with 8 in. height limitation .....	37
Figure 4.2 – A metal thru truss with an inboard railing .....	39
Figure 4.3 – ODOT two-tube railing inside of a Metal 6 railing .....	40
Figure 4.4 – Washington D.C. curb railing .....	41
Figure 4.5 – Workable zone of a reinforced concrete railing .....	46
Figure 4.6 – Cross-section of the TxDOT T221 railing .....	47
Figure 4.7 – Historic bridge with a Bush-Hammered Panel railing .....	48
Figure 4.8 – Cross-section of the Bush-Hammered Panel railing .....	48
Figure 4.9 – Cross-section of a retrofit Bush-Hammered Panel railing .....	49
Figure 4.10 – Elevation view of the retrofit Bush-Hammered Panel railing .....	50
Figure 4.11 – Retrofit Bush-Hammered Panel on a historic concrete arch bridge .....	50
Figure 4.12 – Close-up view of the retrofit Bush-Hammered Panel railing .....	51
Figure 4.13 – Stone 1 railing .....	52
Figure 4.14 – Stone 2 railing .....	52
Figure 4.15 – Stone 3 railing .....	52

Figure	Page
Figure 4.16 – Stone 4 railing.....	53
Figure 4.17 – Cross-section of the concrete beam and post railing.....	54
Figure 4.18 – Concrete 11 railing.....	54
Figure 4.19 – ODOT concrete beam and post modified to approximate Concrete 11 .....	55
Figure 4.20 – ODOT metal tube railing cross-sections .....	56
Figure 4.21 – Metal thru truss with a railing ineligible for replication.....	57
Figure 4.22 – Close-up of Metal 14 railing (light green).....	57
Figure 4.23 – Modified ODOT two-tube railing on a metal thru truss.....	58
Figure 4.24 – Metal 6 railing on historic pony truss bridge.....	59
Figure 4.25 – Modified ODOT two-tube railing .....	59
Figure 4.26 – Application of distributed load on a pedestrian railing .....	61
Figure 4.27 – Rendering of the TxDOT PR3 railing .....	62
Figure 4.28 – Rendering of the ODOT Pedestrian Rail.....	62
Figure 4.29 – Flowchart for selecting a retrofit strategy .....	64

## **ABSTRACT**

Clauss, Adam J. M.S.C.E., Purdue University, December 2014. Strategies for the Replacement of Historic Bridge Guardrails. Major Professor: Robert J. Frosch.

Bridges that are designated historic present a special challenge to bridge engineers whenever rehabilitation work or improvements are made to the bridges. Federal and state laws protect historically significant bridges, and railings on these bridges can be subject to protection because of the role they play in aesthetics. Unfortunately, original railings on historic bridges do not typically meet current crash-test requirements and typically do not meet current standards for railing height and size of permitted openings. The objective of this study is to develop strategies that can be used to address existing railings on historic bridges and to develop solutions that meet current design requirements. To achieve this objective, three phases of research were conducted. First, an overview of current practice for addressing historic bridge railings was performed. Second, an investigation was conducted to document historic bridge railings in Indiana. Finally, rehabilitation solutions were developed to address the specific bridge railings found in Indiana. Based on this research, three retrofit strategies were developed which include an inboard railing, curb railing, and a simulated historic railing. These rehabilitation solutions can be used to address historic bridge railings not only in Indiana, but across the country.



## CHAPTER 1. INTRODUCTION

### 1.1 **Background**

The National Historic Preservation Act of 1966 authorized the creation of the National Register of Historic Places (NRHP). The passage of this law provided a legal means for recognizing historic assets, including bridges. The law also promoted awareness of preserving historic bridges (NPS 2014). Historic bridges are characterized by design philosophies, building techniques, and architectural styles that are uncommon today or sometimes no longer used. Therefore, it is advantageous to preserve historic bridges, which are considered rich cultural icons.

Although historic bridges are visual reminders of bygone eras, they generally do not meet current standards for roadway width, structural adequacy, and railing strength (Buth et al. 2004). Considering railings in particular, the original railing on a historic bridge is not likely to meet current crash test requirements. Historic bridge railings are also not likely to meet current standards for railing height and size of permitted openings.

## **1.2 Objective and Scope**

The objective of this research is to develop a toolbox of design and rehabilitation solutions that can be used to improve the safety of a variety of existing railings on historic bridges in Indiana without damaging the aesthetic qualities or historic value of the bridges. This research was conducted in three phases. First, current practice for addressing historic bridge railings was reviewed. Second, an investigation was conducted to document and inventory historic bridge railings in Indiana. Finally, rehabilitation solutions were developed to address the specific historic bridge railings found in Indiana.

## CHAPTER 2. REVIEW OF HISTORIC BRIDGE RAILING PRACTICE

### 2.1 History of Railing Design Standards

The American Association of State Highway and Transportation Officials (AASHTO) has published bridge design specifications since 1931, but the advent of standard safety and strength requirements for bridge railings occurred in the late 1980s (Barker and Puckett 2013). Development of a set of standard strength and safety requirements for bridge railings was necessary to ensure the safe use of the nation's bridges.

Since August 1986, the Federal Highway Administration (FHWA) has required bridge railings used on projects funded fully or partially with federal money to meet full-scale crash-test criteria (FHWA 2014). The National Cooperative Highway Research Program (NCHRP) published *NCHRP Report 350: Recommended Procedures for the Safety Performance Evaluation of Highway Features* in 1993. This report synthesized previous research on the impact performance of highway barriers and set forth a scheme of Test Levels (TL) for rating the crashworthiness of highway barriers (including bridge railings). This report is the foundation for current crash test and impact performance standards for bridge railings (NCHRP 1993).

In 1994, AASHTO published the *LRFD Bridge Design Specifications 1<sup>st</sup> Ed.* This was the first AASHTO bridge design code to contain strength requirements for bridge railings (AASHTO 1994).

## **2.2 Current Railing Design Standards**

The AASHTO *Manual for Assessing Safety Hardware* (MASH) contains current strength and safety requirements for bridge railings. AASHTO incorporated the content of NCHRP Report 350 into MASH (AASHTO 2009). NCHRP Report 350 prescribed six Test Levels (Test Levels 1 through 6) to quantify the sturdiness of highway barriers against impact, and they are incorporated into MASH. Bridge railings are a subset of highway barriers and are therefore subject to these requirements (NCHRP 1993). Consequently, a new bridge railing must be designed using prescribed forces, and it must be crash tested to determine its Test Level (AASHTO 2009).

The requirements to meet a certain Test Level increase with the numeric value of the Test Level: Test Level 1 is the least demanding while Test Level 6 is the most demanding. Therefore, a railing rated at Test Level 1 has the weakest classification and a railing rated at Test Level 6 has the strongest classification. A new bridge railing is crash tested with multiple vehicles in separate tests, as shown in Table 2.1. Crash tests of a bridge railing are evaluated using three criteria: structural adequacy of the railing, occupant risk (to the impacting vehicle), and post-impact vehicular response. A Test Level is assigned to a railing based on the application of the criteria to the results of crash tests (NCHRP 1993).

In the 16 years from the publication of NCHRP Report 350 to the publication of MASH, some changes were made to the Test Level requirements. The Test Level requirements are shown in Table 2.1 (AASHTO 2014). In Table 2.1,  $W$  is vehicle weight,  $B$  is out-to-out wheel spacing on an axle, and  $G$  is height of the vehicle's center of gravity. Bridge railings that were crash-tested and accepted under the NCHRP Report 350 criteria are considered appropriate as replacements or as new installations (FHWA 2014).

**Table 2.1 – Changes from NCHRP Report 350 to AASHTO MASH (AASHTO 2014)**

	Vehicle Characteristics	Small Automobiles		Pickup Truck	Single-Unit Van Truck	Van-Type Tractor Trailer		Tractor-Tanker Trailer
NCHRP Report 350	W (kips)	1.55	1.8	4.5	18.0	50.0	80.0	80.0
	B (ft)	5.5	5.5	6.5	7.5	8.0	8.0	8.0
	G (in.)	22	22	27	49	64	73	81
	Crash angle, $\theta$	20°	20°	25°	15°	15°	15°	15°
	Test Level	Test Speeds (mph)						
	TL-1	30	30	30	N/A	N/A	N/A	N/A
	TL-2	45	45	45	N/A	N/A	N/A	N/A
	TL-3	60	60	60	N/A	N/A	N/A	N/A
	TL-4	60	60	60	50	N/A	N/	N/A
	TL-5	60	60	60	N/A	N/A	50	N/A
	TL-6	60	60	60	N/A	N/A	N/A	50
AASHTO MASH	W (kips)	2.42	3.3	5.0	22.0	N/A	79.3	79.3
	B (ft)	5.5	5.5	6.5	7.5	N/A	8.0	8.0
	G (in.)	N/A	N/A	28	63	N/A	73	81
	Crash angle, $\theta$	25°	N/A	25°	15°	N/A	15°	15°
	Test Level	Test Speeds (mph)						
	TL-1	30	N/A	30	N/A	N/A	N/A	N/A
	TL-2	45	N/A	45	N/A	N/A	N/A	N/A
	TL-3	60	N/A	60	N/A	N/A	N/A	N/A
	TL-4	60	N/A	60	N/A	N/A	N/A	N/A
	TL-5	60	N/A	60	N/A	N/A	50	N/A
	TL-6	60	N/A	60	N/A	N/A	N/A	50

In addition to structural rigidity requirements, bridge railings are required to have a minimum height above the wearing surface. Section 13.7.3.2 of AASHTO's *LRFD Bridge Design Specifications 7<sup>th</sup> Ed.* lists bridge railing height requirements. Railings rated TL-3 or lower must be at least 27 in. tall. Railings rated at TL-4 must be at least 32 in. tall and railings rated at TL-5 must be at least 42 in. tall. Finally, railings rated at TL-6 must be at least 90 in. tall (AASHTO 2014). A summary of these requirements is provided in Table 2.2.

**Table 2.2 – Summary of railing height requirements**

<b>Rating</b>	<b>Minimum Railing Height (in.)</b>
TL-3 or lower	27
TL-4	32
TL-5	42
TL-6	90

### **2.3 Historic Bridge Identification**

The passage of the National Historic Preservation Act in 1966 authorized the creation of the National Register of Historic Places (NPS 2014). To be eligible for listing on the NHRP, a historic asset must retain sufficient integrity, be at least 50 years old, and have significance under one or more of the following criteria:

Criterion A: A resource may be eligible under this criterion if it is associated with events that have made a significant contribution to the broad patterns of history.

Criterion B: A resource may be eligible under this criterion if it is associated with the lives of persons significant in our past.


Criterion C: A resource may be eligible under this criterion if it embodies the distinctive characteristics of a type, period, or method of construction, or if it represents the work of a master, or if it possesses high artistic values.

Criterion D: A resource may be eligible under this criterion if it has yielded, or is likely to yield information important in prehistory or history.

Bridges are typically eligible under Criterion A or Criterion C (ODOT 2007).

## **2.4 National Historic Bridge Management**

In 1987, Congress passed the Surface Transportation & Uniform Relocation Assistance Act (STURAA). A stipulation of STURAA requires states to inventory their historic bridges. In 2012, the consulting firm Mead & Hunt (M&H) published *Historic Bridge Practices Nationwide: Inventory, Evaluation, and Management*. The M&H report detailed historic bridge practices in the U.S. M&H surveyed the Departments of Transportation (DOTs) of all 50 states to determine the progress of the states' historic bridge inventories. M&H presented its survey results in the bar chart shown in Figure 2.1 (Mead & Hunt 2012).



**Figure 2.1 – States’ historic bridge management activities (Mead & Hunt 2012)**

Although all 50 states have inventoried their historic bridges, Figure 2.1 indicates that only 38 states have completed historic bridge rehabilitation projects. The historic bridge rehabilitation projects ranged from minor repairs to multi-million-dollar projects. Additionally, fewer than half of the 50 states have initiated programmatic agreements or management plans. Programmatic agreements and management plans are methods for states to identify historic bridges, identify preservation options, and coordinate federal funding for proposed projects (Mead & Hunt 2012).



Indiana is among the 19 states that have executed a programmatic agreement to manage its historic bridges. INDOT executed a programmatic agreement with FHWA, the Indiana State Historic Preservation Officer (SHPO), and the Advisory Council on Historic Preservation in July 2006 (INDOT 2006).

Elsewhere, the Oregon Department of Transportation (ODOT) has completed a number of successful rehabilitations (Mead & Hunt 2012). Kentucky, Ohio, Oregon, Tennessee, and Texas are a few states that have published documents outlining their historic bridge preservation efforts.

1. Kentucky: *Assessment of Kentucky's Historic Truss Bridges* (O'Connell et al. 2010).
2. Ohio: *Ohio Historic Bridge Maintenance and Preservation Guide* (TranSystems 2010).
3. Oregon: *Historic Bridge Preservation Plan* (ODOT 2007).
4. Tennessee: *Tennessee's Survey Report for Historic Highway Bridges* (Carver 2008).
5. Texas: *Historic Bridge Manual* (TxDOT 2010)

More general guidance on historic bridge preservation is available in the following publications:

1. *Guidelines for Historic Bridge Rehabilitation and Replacement* (AASHTO 2008).
2. *NCHRP Synthesis 275: Historic Highway Bridge Preservation Practices* (NCHRP 1999).

3. *Best Practices and Lessons Learned on the Preservation and Rehabilitation of Historic Bridges* (Parsons Brinckerhoff 2012).

## **2.5 Bridge Railing Manual**

The Texas Department of Transportation (TxDOT) developed a manual specifically for bridge railings (TxDOT *Bridge Railing Manual*). The manual summarizes current policies governing the use of bridge railings in Texas and provides information on acceptable Texas bridge railing types. Of particular interest, a section of the manual is devoted to railings on historic bridges. It presents four options that can be used to upgrade the railings on historic bridges in Texas. These four options are summarized as:

1. Place an approved railing inboard of the existing railing and leave the existing railing undisturbed.
2. Replace the existing railing with an acceptable approved railing, approximating the appearance of the old railing with the new railing.
3. Remove the existing railing and incorporate it into a new acceptable railing.
4. Design a special railing to closely match the appearance of the existing railing.

The difference between Options 2 and 4 is the degree to which a historic railing is approximated. Option 4 calls for a new railing to be designed to look almost exactly like the historic railing while Option 2 calls for finding an existing railing that resembles the historic railing. Option 2 may not be available for many types of railings (TxDOT 2012).

## **2.6 Historic Bridge Railing Research**


Texas leads the country in historic bridge railing research. The Texas Transportation Institute (TTI), with the support of the Texas Department of Transportation (TxDOT), has been at the forefront of historic bridge railing retrofit research. TTI engineers have designed, crash-tested, and implemented retrofit railings on some of Texas's on-system (carrying state highways) truss bridges (Buth et al. 2004).

TxDOT formed a Historic Bridge Task Force in 1996. The task force developed a methodology for evaluating preservation options for on-system truss bridges that are listed on or are eligible for listing on the National Register of Historic Places (NRHP). In 2003, TxDOT maintained 38 metal truss bridges aged 50 years or more on its state highway system. A total of 33 of the 38 bridges are listed on the NRHP. The existing railings on these bridges did not meet MASH requirements. In addition, these bridges have other problems common to many types of historic bridges, including narrow deck widths, low vertical clearance, and substandard load capacities (Buth et al. 2004).

TxDOT focused on developing solutions for its on-system truss bridges. A research program performed at TTI addressed the substandard attributes of the railings on the 38 truss bridges (Buth et al. 2004). In particular, they focused on two of their on-system truss bridges as outlined by the following research objectives:

1. Design/develop a retrofit railing for low-speed application on the Roy B. Inks Bridge in Llano, Texas. The Roy B. Inks Bridge has four main spans consisting of Parker thru trusses with a speed limit of 40 mph and is shown in Figure 2.2.

2. Design/develop a retrofit railing for high-speed application on the U.S. 281 Bridge over the Brazos River in Palo Pinto County, Texas. The U.S. 281 Bridge is a three-span Warren thru-truss bridge with a speed limit of 60 mph and is shown in Figure 2.3 (Buth et al. 2004).




**Figure 2.2 – Roy B. Inks Bridge (Buth 2004)**



**Figure 2.3 – U.S. 281 Bridge (Buth 2004)**

In both bridges, a continuous steel channel served as the railing. In the original configuration, the channel member railing was mounted directly to the truss members as shown in Figure 2.4 for the Roy B. Inks Bridge. The U.S. 281 bridge had a similar railing connection detail. Engineers at TTI designed retrofit railings for these bridges using the impact conditions specified in the *AASHTO LRFD Bridge Design Specifications 2<sup>nd</sup> Ed.* (Buth et al. 2004).




**Figure 2.4 – Typical railing connection to truss member on the Roy B. Inks Bridge (Williams 2010)**

Each retrofit railing utilized the original channel member to maintain the historic appearance of the bridges. For the low-speed retrofit railing (40 mph, Roy B. Inks Bridge), a TS8x4x1/2 section was added to the C12x20.7 to increase the overall flexural capacity of the railing. Additionally, engineers placed crushable steel tube blockouts between the composite C12x20.7 and TS8x4x1/2 railing and the truss members to absorb impact forces and protect the truss members. Figure 2.5 shows the railing before it was tested while Figure 2.6 shows the railing after crash testing (Buth et al. 2004).



**Figure 2.5 – Test setup of the Roy B. Inks railing before crash testing (Buth et al. 2004)**



**Figure 2.6 – Test setup of the Roy B. Inks railing after crash testing (Buth et al. 2004)**

The steel blockout deformed during the test as expected. This railing was successfully crash-tested for Test Level 2 (Buth et al. 2004). Figure 2.7 shows the Roy B. Inks Bridge after the railing was retrofitted (Williams 2010).



**(a) Railing Profile (Google 2013)**

**(b) Blockout (Williams 2010)**

**Figure 2.7 – Roy B. Inks bridge with the retrofit railing developed at TTI**

For the high-speed retrofit railing (60 mph, U.S. 281 Bridge), the C12x20.7 was mounted on the front of a W6x20 section to improve the overall flexural strength of the railing. W6x20 steel posts anchored the new W6x20-C12x20.7 composite railing to the existing curb, rather than to the truss members as was done in the Roy B. Inks Bridge. Figure 2.8 shows the composite railing before the crash test while Figure 2.9 shows the railing after testing (Buth et al. 2004).





**Figure 2.8 – Test setup of the U.S. 281 railing before crash testing (Buth et al. 2004)**



**Figure 2.9 – Test setup of the U.S. 281 railing after crash testing (Buth et al. 2004)**

The railing was successfully crash-tested for Test Level 3 (Buth et al. 2004). According to John Holt of the Texas Department of Transportation, the retrofit railing had not yet been installed on the U.S. 281 bridge as of October 2014.

Considering that new truss bridges are being built in Texas, TxDOT wants to offer flexibility for designers to choose between railings supported by the concrete bridge deck or railings supported directly by the truss members. The successful completion of this research program not only resulted in suitable retrofit railings for historic metal truss bridges, it also resulted in additional design options for bridge engineers (Buth et al. 2004). These options are consistent with Option 3 discussed in the TxDOT *Bridge Railing Manual*.




## 2.7 Historic Replacement Railings


Texas has developed standardized railings that are designed to match the appearance of historic concrete railings (Option 4 of the historic railing option list in the TxDOT *Bridge Railing Manual*). The standardized railings include TxDOT T411, TxDOT C411, and TxDOT C412. Illustrations of these railings are shown in Figure 2.10 and Table 2.3 provides a summary of the TxDOT railings. The T411 was designed as a traffic railing while the C411 and C412 were designed as pedestrian/traffic combination railings (TxDOT 2012). Standard drawings of these railings are provided in Appendix A.

**Table 2.3 – TxDOT standardized historic approximation railings**


<b>Railing</b>	<b>Height (in.)</b>	<b>Rating</b>
TxDOT T411	32	TL-2
TxDOT C411	42	TL-2
TxDOT C412	42	TL-4



**(a) TxDOT T411**




**(b) TxDOT C411**



**(c) TxDOT C412**

**Figure 2.10 – TxDOT approximation of historic bridge railings (TxDOT 2012)**

To provide a historic railing for use in Indiana, INDOT adopted the TxDOT C411 railing. In Indiana, the TxDOT C411 is known as the INDOT TX railing. An illustration of the INDOT TX railing is shown in Figure 2.11 while Figure 2.12 shows an Indiana bridge that implemented this railing. Standard drawings of the INDOT TX railing are also provided in Appendix A.



**Figure 2.11 – INDOT TX railing profile (INDOT 2014)**



**Figure 2.12 – INDOT TX railing installation**

## **2.8 Modern Aesthetic Railings**

Other aesthetic bridge railings, in addition to railings that were designed to explicitly match a type of historic railing, have been developed and installed on bridges in the U.S. The California Department of Transportation (Caltrans) has numerous examples of aesthetic railings on its state highway system, as illustrated in Figures 2.13 through 2.16 (Caltrans 2014).

Caltrans discusses the possibilities for California bridge railings in its publication *Bridge Rails and Barriers* (Caltrans 2014). The artistry of the ornate railings on California bridges pays homage to historic bridges while satisfying modern strength and safety requirements (Caltrans 2014). These railings may also provide aesthetic solutions for historic bridges.



**Figure 2.13 – Concrete railing with tribal design architectural texture (Caltrans 2014)**



**Figure 2.14 – Concrete railing with tribal design architectural texture (Caltrans 2014)**



**Figure 2.15 – Concrete railing with architectural treatment (Caltrans 2014)**





**Figure 2.16 – Concrete railing with architectural treatment (Caltrans 2014)**

## **2.9 Railing Approval**

Generally, a historical preservation agency has jurisdiction over proposed alterations to historic assets. In Indiana, alterations to historic assets must be approved by the Indiana State Historic Preservation Officer (SHPO). Therefore, for railing changes on a historic bridge, the responsible transportation agency must apply to Indiana SHPO for approval. While INDOT is directly responsible for historic bridges on state or U.S. highways, the majority of historic bridges in Indiana are on either municipal or county roads. When federal funding is utilized to alter a historic bridge on a municipal or county road, INDOT has oversight of the process.

## **CHAPTER 3. DOCUMENTATION OF HISTORIC BRIDGES AND RAILINGS IN INDIANA**

### **3.1 Indiana Historic Bridge Database**

After INDOT began its programmatic agreement with FHWA in 2006, the historic bridges in Indiana were required to be identified. INDOT contracted Mead & Hunt (M&H) to apply the National Register of Historic Places (NRHP) criteria to all bridges in the state. Mead & Hunt completed a database, took photographs of Indiana's historic bridges, and delivered its findings to INDOT in March 2008. After two years of public input and revision, M&H delivered its final database to INDOT in December 2010. The database indicated that Indiana had 796 historic bridges as of December 2010. Of the 796 historic bridges, 705 were still in service in December 2010.

### **3.2 Analysis of the Historic Bridge Database**

Using the database and photos compiled by M&H, a streamlined spreadsheet of Indiana's historic bridges was compiled. The spreadsheet was designed to include the following:

- Location by county
- National Bridge Inventory (NBI) number
- Structure type
- Railing type

- Railing-to-deck connection type
- Facility carried
- Facility crossed
- Qualifying historic significance parameter

As part of its programmatic agreement with the FHWA, INDOT is required to publish annual reports of its historic bridge activities. The first report covered the calendar year of 2010 and was published in January 2011. This report and subsequent annual reports (calendar years 2011, 2012, 2012 addendum, 2013) delivered under the programmatic agreement indicated that 47 of the 705 in-service historic bridges have been closed to traffic or replaced between December 2010 and January 2014 (INDOT 2014). A list of historic bridges that have been removed from service between December 2010 and January 2014 is provided in Appendix B.

As of January 2014, there were 658 in-service historic bridges in Indiana (INDOT 2014). Most of the railings on the 658 bridges do not meet the *Manual for Assessing Safety Hardware* (MASH) requirements for strength and impact performance due to differences in the design requirements of the time as well as varying states of disrepair.

The spreadsheet of historic bridges was analyzed to determine statistics for the following items:

1. Type of structure
2. Facility carried
3. Facility crossed
4. Railing type

Four breakdowns of the historic bridge inventory were generated for the historic bridges that remain in service (658 bridges). Information on numbers of each structure type, facility carried, and facility crossed are presented in Tables 3.1 through 3.3. The nomenclature in the left-most columns of Tables 3.1 to 3.3 is as presented by M&H. As indicated from review of the data, the majority of Indiana's in-service historic bridges (approximately 58%) are comprised of three types: concrete arch, metal pony truss, and metal thru truss bridges. The majority of Indiana's in-service historic bridges are on county roads or city streets with only a small percentage (13%) carrying either a state or a U.S. highway. Finally, the majority cross small waterways.

**Table 3.1 – In-Service Historic Bridges by Structure Type**

Category	In-Service Bridges		Out-of-Service Bridges
	Quantity	Percentage	Quantity
Concrete Arch	175	26.6	9
Metal Arch	6	0.9	1
Metal Pony Truss	88	13.4	36
Metal Thru Truss	121	18.4	52
Prestressed Concrete Box Beam	11	1.7	1
Prestressed Concrete I-Beam	9	1.4	0
Reinforced Concrete Girder and Beam	79	12.0	4
Reinforced Concrete Rigid Frame and Box	6	0.9	1
Reinforced Concrete Slab	41	6.2	7
Steel Beam	17	2.6	1
Steel Deck Truss	8	1.2	0
Steel Girder	9	1.4	7
Steel Movable	1	0.1	0
Stone Arch	34	5.2	4
Timber Other	1	0.1	3
Timber Truss	52	7.9	12
<b>Total</b>	<b>658</b>	<b>100%</b>	<b>138</b>
<b>Grand Total of Historic Bridges</b>	<b>796</b>		



**Table 3.2 – In-Service Historic Bridges by Facility Carried**

Facility Carried	In-Service Bridges	
	Quantity	Percentage
County Road	260	39.5
Named Street	317	48.2
State Highway	48	7.3
U.S. Highway	33	5.0
<b>Total</b>	<b>658</b>	<b>100%</b>

**Table 3.3 – In-Service Historic Bridges by Facility Crossed**

Facility Crossed	In-Service Bridges	
	Quantity	Percentage
Named Street	3	0.5
State Highway	1	0.2
U.S. Highway	2	0.3
Creek	396	60.2
Ditch	28	4.3
Railroad	13	2.0
River	156	23.7
Canal	5	0.8
Other (Run, Branch, Fork, Hollow, Whitewater, Reservoir, Lake, Tunnel, Stream, Drain, Bayou)	54	8.2
<b>Total</b>	<b>658</b>	<b>100%</b>

The types of railings were not identified by M&H. Therefore, this study developed a naming system for the railings. This nomenclature is presented in Table 3.4 and images of each railing type are provided in Appendix C. In all, 61 different railing types were identified. Using this system, the railing types for each bridge were identified and the results are presented in Table 3.5.

**Table 3.4 – Railing types**

<b>Railing</b>		<b>Description</b>
<b>Concrete</b>	1 (Bush-Hammered Panel)	Concrete railing with sunk-in panels of aspect ratio greater than one (length / height)
	2	Concrete railing with rectangular outlines of aspect ratio greater than one (length / height)
	3	Concrete railing with sunk-in panels of aspect ratio approximately one (length / height)
	4	Concrete railing with capital block and posts
	5	Concrete railing with sunk-in archways
	6	Concrete railing with arch openings and posts
	7	Concrete railing with urn-shaped blocks and posts
	8	Concrete railing with diamond openings
	9	Concrete railing with ovular open blocks with capital blocks and posts
	10	Concrete railing with wide arch openings and posts
	11	Concrete railing with tall arch openings
	12	Concrete railing with rectangular openings of aspect ratio greater than one (length / height)
	13	Concrete railing with rectangular openings of aspect ratio greater than one (length / height) and posts
	14 (F-type)	F-type concrete railing
	15	Vertical face concrete parapet wall
	16	Two-tiered vertical face concrete railing with posts
	17	Two-tiered vertical face concrete railing without posts
	18	Three-tiered concrete railing with or without posts
	19	Three-tiered concrete railing with setbacks
	20	Three-tiered concrete railing with longitudinal outlines and end treatments
	21	Vertical face concrete parapet wall with capital block
	22	Concrete railing with thinner middle section
	23	Concrete railing with large blocks and posts and capital block
	24	Concrete railing consisting of trapezoidal sections with triangular openings
	25	Concrete railing with red brick facade and posts #1
	26	Concrete railing with red brick facade and posts #2

**Table 3.4 Continued**

<b>Metal</b>	1	Three-tube semi-ovular metal railing
	2	Two-tube semi-ovular metal railing
	3	Two-bar rectangular metal railing without concrete parapet
	4	Single serif channel metal railing
	5 (Galvanized Beam)	Galvanized w-beam metal railing
	6	Metal lattice railing
	7	Single sans-serif channel metal railing
	8	Single rectangular tube metal railing
	9	Double rectangular tube metal railing
	10	Double angle metal railing
	11	Single angle metal railing
	12	Two-bar circular metal railing with posts
	13	Three-bar circular metal railing with posts
	14	Two-bar metal railing with fence posts
<b>Metal and Concrete</b>	1	Two-bar circular metal railing on top of a concrete parapet
	2	Two-bar square metal railing on top of a concrete parapet
	3	Two-bar circular metal railing with concrete posts
	4 (F-type w/ Handrail)	F-type concrete railing with a metal handrail on top
<b>Pedestrian</b>	1	Decorative metal fence railing #1 (with concrete posts)
	2	Decorative metal fence railing #2 (with concrete posts)
	3	Decorative metal fence railing #3 (with concrete posts)
	4	Decorative metal fence railing #4 (with concrete posts)
	5	Decorative metal fence railing #5 (without concrete posts or very few concrete posts)
	6	Decorative metal fence railing #6 (without concrete posts or very few concrete posts)
	7	Decorative metal fence railing #7 (without concrete posts or very few concrete posts)
	8	Decorative metal fence railing #8 (without concrete posts or very few concrete posts)

**Table 3.4 Continued**

<b>Stone</b>	1	Round stone and mortar railing
	2	Rectangular stone vertical face railing
	3	Rectangular stone vertical face railing with capital stones
	4	Rectangular stone vertical face railing with capital stones and stone posts
	5	Rectangular interlocking stone blocks with rectangular openings
	6	Stone block railing with diamond openings (similar to Concrete 8)
<b>Timber</b>	1	Single-board timber railing
	2	Double-board timber railing
	3	Triple-board timber railing
	No Railing	No railing

**Table 3.5 – Historic bridges by railing type**

<b>Historic Bridge Railing Type</b>		<b>Quantity</b>	<b>Percentage</b>
<b>Concrete</b>	1 (Bush-Hammered Panel)	74	11.25
	2	46	7.00
	3	2	0.31
	4	2	0.31
	5	1	0.15
	6	39	5.93
	7	12	1.82
	8	1	0.15
	9	1	0.15
	10	2	0.31
	11	1	0.15
	12	2	0.31
	13	1	0.15
	14 (F-type)	14	2.11
	15	24	3.65
	16	2	0.31
	17	6	0.91
	18	6	0.91
	19	4	0.61
	20	1	0.15
	21	3	0.46
	22	1	0.15
	23	2	0.31
	24	2	0.31
	25	1	0.15
	26	1	0.15
<b>Metal</b>	1	15	2.28
	2	9	1.37
	3	1	0.15
	4	1	0.15
	5 (Galvanized Beam)	75	11.40
	6	78	11.85
	7	9	1.37
	8	2	0.31

Table 3.5 Continued

<b>Metal (Continued)</b>	9	24	3.65
	10	38	5.78
	11	1	0.15
	12	6	0.91
	13	1	0.15
	14	7	1.06
<b>Metal and Concrete</b>	1	8	1.22
	2	2	0.31
	3	1	0.15
	4 (F-type w/ Handrail)	1	0.15
<b>Pedestrian</b>	1	1	0.15
	2	1	0.15
	3	1	0.15
	4	1	0.15
	5	1	0.15
	6	2	0.31
	7	1	0.15
	8	1	0.15
<b>Stone</b>	1	1	0.15
	2	10	1.51
	3	13	1.98
	4	1	0.15
	5	3	0.45
	6	1	0.15
<b>Timber</b>	1	47	7.14
	2	6	0.91
	3	2	0.31
<b>Name</b>	No Railing	35	5.32
<b>Total</b>		<b>658</b>	<b>100%</b>

From review of Table 3.5, it is clear that some railing types are more common than others. Twenty-five railing types are evident on only a single historic bridge in the state, and 11 railing types are evident on only two historic bridges. Of particular interest is that only seven railing types have a percentage of 5% or greater. Furthermore, no railing whatsoever was observed on 5.3% of the bridges. The categories with more than 5% occurrence are highlighted in Table 3.5, summarized in Table 3.6, and illustrated in Figures 3.1 to 3.8. The railings are ranked in terms of the highest occurrence. While there were 61 different types of railings identified, the top seven railings constitute 2/3 of all railings in use (Table 3.6). Based on this analysis, focusing retrofit strategies on a small number of railing types can have a significant impact. While the timber railings, and in particular Timber 1, constitute a large quantity of bridges, this railing type, which is predominantly on covered bridges, is considered outside the scope of this study and therefore will not be considered further.

**Table 3.6 – Summary of railing types observed on 5% or more of bridges**

<b>Rank</b>	<b>Historic Bridge Railing Type</b>	<b>Quantity</b>	<b>Percentage</b>
1	Metal 6	78	11.85
2	Metal 5 (Galvanized Beam)	75	11.40
3	Concrete 1 (Bush-Hammered Panel)	74	11.25
4	Timber 1	47	7.14
5	Concrete 2	46	7.00
6	Concrete 6	39	5.93
7	Metal 10	38	5.78
8	No Railing	35	5.32
<b>Total</b>		<b>432</b>	<b>65.67%</b>



**Figure 3.1 – Metal 6 railing (Rank 1)**



**Figure 3.2 – Metal 5 (Galvanized Beam) railing (Rank 2)**



**Figure 3.3 – Concrete 1 (Bush-Hammered Panel) railing (Rank 3)**



**Figure 3.4 – Timber 1 railing (Rank 4)**





**Figure 3.5 – Concrete 2 railing (Rank 5)**



**Figure 3.6 – Concrete 6 railing (Rank 6)**



**Figure 3.7 – Metal 10 railing (Rank 7)**



**Figure 3.8 – Bridges with no railing (Rank 8)**

## **CHAPTER 4. BRIDGE RAILING RETROFIT STRATEGIES**

### **4.1 Introduction**

Three different retrofit strategies for guardrails on Indiana's historic bridges were identified. Research focused on developing solutions that can be immediately used, rather than developing completely new railings that require crash-testing programs. Therefore, all solutions are based on previously crash-tested and accepted bridge railings.

Avoidance of crash testing is not unprecedented. Frederick G. Wright Jr. of the Federal Highway Administration (FHWA) discussed how guardrails may be admissible without crash test programs in a May 16, 2000 memorandum to FHWA Resource Center directors and division administrators. He discussed a railing design and analysis project undertaken by the Colorado Department of Transportation (CDOT). CDOT designed a new railing which was similar to a previously crash tested and accepted railing. CDOT then analyzed the capacity of the previously accepted railing and modified its design to ensure it possessed the same strength. FHWA accepted the new CDOT railing without crash testing (Wright Jr. 2000).

Bridge engineers are permitted to use this type of analysis as a basis for acceptance of bridge railings that are similar to a design that has been accepted under NCHRP Report 350/MASH guidelines. Mr. Wright expressed a desire to provide highway agencies a greater choice of railing designs without requiring unnecessary testing. He also cautioned that all possible railing failure modes must be considered carefully when this type of analysis is utilized (Wright Jr. 2000).

#### **4.2 Bridge Railing Design Parameters**

Before a retrofit strategy can be chosen, two bridge railing design parameters must be considered. The two parameters are the Test Level (TL) required and the presence/absence of a sidewalk. In Indiana, all new bridges and bridge retrofits are subject to the requirements of the current edition of the *Indiana Design Manual* (IDM). Chapter 404, “Bridge Deck” provides details on the design of bridge railings.

The Test Level (TL) required is a function of the design speed of the facility carried, the Annual Average Daily Traffic (AADT), the percentage of trucks on the facility carried, the bridge railing offset, the geometry of the bridge and adjacent sections of roadway, the height of the bridge deck, and the type of land use below the bridge (INDOT 2013). The AADT and percentage of trucks of the AADT must be known in order to use the IDM to ascertain the required railing Test Level (TL) for a bridge.

The presence or absence of a sidewalk also controls the type of railing that can be specified. If a sidewalk is present, a 42-in. tall railing is required. Additionally, the design speed on a bridge affects the type of required railing(s).

#### 4.2.1 Required Test Level

The *Indiana Design Manual* (IDM) considers only three of the six AASHTO-prescribed Test Levels: TL-2, TL-4, and TL-5. The IDM contains the complete procedure for determining the required TL, and this procedure is provided in IDM Chapter 404 (INDOT 2013).

TL-2: Generally appropriate on a bridge which is not on the state highway system or on a bridge that is on the state highway system and has a design speed of 45 mph or lower.

TL-4: Generally appropriate on a bridge which does not meet the criteria for a TL-2 railing or for a bridge that is on the state highway system and has a design speed of 50 mph or higher.


TL-5: Generally appropriate on a bridge that is on the state highway system and has a high AADT or a high percentage of truck traffic.

In the instance that a bridge railing is rated at TL-4, but the IDM procedure calls for a TL-5 railing, it is acceptable to leave the TL-4 railing in place “for a minor bridge rehabilitation project which does not include bridge deck replacement or deck widening.” The TL-4 railing must be replaced by a TL-5 railing if the rehabilitation project involves deck replacement or deck widening (INDOT 2013).

#### 4.2.2 Presence/Absence of a Sidewalk

The presence/absence of a sidewalk on a bridge affects the type of railing that can be installed in a retrofit project. If a sidewalk is present, either of the two following conditions applies to the railing selection for a bridge, based on design speed (INDOT 2013).

*Design speed of 45 mph or lower:* Only a railing shown to be crashworthy in the presence of a sidewalk may be chosen. A pedestrian/traffic combination railing must be selected. A pedestrian/traffic combination railing is a railing that satisfies the Test Level requirement due to the adjusted AADT and satisfies the height requirement for a pedestrian railing, which is at least 42 in., measured from the surface of the walkway. The railing is required to be placed at the coping. Furthermore, Section 13.11.2 of the *AASHTO LRFD Bridge Design Specifications 7<sup>th</sup> Ed.* requires that a barrier curb, not exceeding 8 in. in height, separate the sidewalk from the roadway (AASHTO 2014). Figure 4.1 shows a typical barrier curb and details the height limitation.



**Figure 4.1 – Typical barrier curb on a bridge with 8 in. height limitation (AASHTO 2014)**

*Design speed of 50 mph or higher:*

A bridge railing must be placed between the sidewalk and the roadway. An accompanying pedestrian railing is required to be placed at the coping. The sidewalk must be laterally protected on both sides. Both the outer pedestrian railing and the inner pedestrian/traffic combination railing shall be at least 42 in. in height, measured from the surface of the walkway. Indiana permits the sidewalk to be at the same elevation of the roadway surface in this instance (INDOT 2013).

#### **4.2.3 Horizontal Roadway Clearance on a Bridge**

Although not a design parameter for railings on new bridges, the horizontal roadway clearance on a historic bridge can be restrictive to remedial efforts. A new bridge can simply be designed to be wide enough to accommodate any bridge railing, but a historic bridge generally cannot be widened. In both rural and urban environments, new bridges or bridges under reconstruction are required to have a roadway clearance equal to the width of the traveled way (12 ft per lane) plus a 10 ft right shoulder and a 4 ft left shoulder (INDOT 2013). Many historic bridges have lanes narrower than 12 ft and shoulders narrower than 4 ft. If a retrofit strategy for a historic bridge railing would infringe upon the horizontal roadway clearance, it cannot be implemented.

### **4.3 Inboard Retrofit**


One retrofit option is to install a modern railing inside of the original railing, and the new railing is referred to as an inboard rail. This technique has previously been used in Indiana as shown in Figure 4.2. In the early 2000s, a metal thru truss carrying State Road 75 across Wildcat Creek in Carroll County, Indiana was retrofitted with the INDOT CF-1, which is equivalent to the Oregon Department of Transportation (ODOT) two-tube curb-mounted railing. The CF-1 railing is no longer a standard in Indiana, but is still standardized in Oregon. The metal tube railing was installed inside of the original railing.

Installing an inboard rail is an attractive option for a bridge that has the necessary horizontal clearance to accommodate it. Another benefit of installing an inboard railing is the ability to choose a railing through which drivers can see the original railing, thus maintaining the historic appearance of the bridge. Unfortunately, many historic bridges have narrow deck widths. An inboard railing cannot be installed on a bridge if it would exacerbate a lane width deficiency.



**Figure 4.2 – A metal thru truss with an inboard railing**

Figure 4.3 shows a rendering of another possible inboard rail. An existing Metal 6 railing can be protected by the ODOT two-tube railing without compromising the historic appearance of the bridge.



**Figure 4.3 – ODOT two-tube railing inside of a Metal 6 railing**

#### **4.4 Curb Retrofit**

A total of 113 historic bridges have sidewalks. In these cases, another retrofit option is to provide an inboard rail that is located at the curb. This railing is known as the Washington D.C. curb railing for its place of origin (FHWA 2014). This option has the advantage of protecting the sidewalk from errant vehicles. Furthermore, INDOT does not require the original railing to be replaced if the curb railing option is exercised. A disadvantage of the Washington D.C. railing, however, is that it is rated at TL-2, meaning it cannot be used on bridges with design speeds of 50 mph or higher.



This may not be a severe disadvantage considering that many historic bridges are on lower design speed roadways. Figure 4.4 shows a rendering and implementation of the Washington D.C. curb railing.



(a) Rendering (b) Implementation  
**Figure 4.4 – Washington D.C. curb railing (FHWA 2014)**

#### **4.5 Railing Replacement**

A third retrofit option is to replace a historic railing with a simulated historic railing. The *Indiana Design Manual* (IDM) allows modern railings to be modified for project-specific use. An advantage of this option is that a railing can be designed to closely match the appearance of a historic railing, although in some cases it may not be possible to design a close approximation.

Modern crash-tested and approved reinforced concrete and metal tube railings were modified to match the appearance of 42 historic railings. Two approaches were used. For reinforced concrete railings, the approved railing cross-section was expanded and altered. For metal tube railings, attachments for the approved railings were designed. The 42 simulated historic railings were designed to satisfy the requirements of the IDM. Three of the historic railing types were timber, and therefore, were outside the scope of this research and not considered.

Sixteen of the observed railings on historic bridges did not possess a historic look, did not possess acceptable geometry under modern crash test standards, and did not exemplify historic craftsmanship; therefore, they were not replicated.

Drawings of the Concrete 1 railing (Bush-Hammered Panel) from circa 1940 were provided by INDOT. These drawings aided the design of a modern railing that approximated this railing. Unfortunately, detailed drawings of other railing types were not available.

Table 4.1 outlines the railings that were approximated as well as those that were not. For railings that were approximated, the crash-tested base railing is listed along with the modification required. For those that were not approximated, the reason for not replicating is provided. Renderings and drawings were produced for each of the 42 historic railings that were approximated with a modern railing. For some historic railings, two simulated railings were developed. A picture of each historic railing, paired with the modern base railing used to approximate it, as well as the simulated railing are provided in Appendix D. Drawings of each simulated railing are included in Appendix E.

**Table 4.1 – Historic railing approximation methods**

	<b>Historic Railing</b>	<b>Base Railing</b>	<b>Approximation Method</b>
<b>Concrete</b>	1 (Bush-Hammered Panel)	TxDOT T221	Custom forms
	2	TxDOT T221	Custom forms
	3	TxDOT T221	Custom forms
	4	TxDOT T221	Custom forms
	5	TxDOT T221	Custom forms
	6	INDOT TX	No modification necessary
	7	ODOT Concrete Beam and Post	Custom forms and infill
	8	ODOT Concrete Beam and Post	Custom forms and infill

**Table 4.1 Continued**

<b>Concrete (Continued)</b>	9	ODOT Concrete Beam and Post	Custom forms and infill
	10	ODOT Concrete Beam and Post	Custom forms and infill
	11	ODOT Concrete Beam and Post	Custom forms and infill
	12	ODOT Concrete Beam and Post	Custom forms and infill
	13	ODOT Concrete Beam and Post	Custom forms and infill
	14 (F-type)	None	This is a modern railing
	15	TxDOT T221	No modification necessary
	16	TxDOT T221	Custom forms and infill
	17	TxDOT T221	Custom forms and infill
	18	TxDOT T221	Custom forms and infill
	19	INDOT FC	Custom forms and infill
	20	TxDOT T221	Custom forms and infill
	21	None	Does not possess historic appearance
	22	ODOT Concrete Beam and Post	Custom forms and infill
	23	TxDOT T221	Custom forms and infill
	24	None	Unfavorable geometry, does not possess historic appearance
	25	TxDOT T221	Masonry attachments
	26	TxDOT T221	Masonry attachments
<b>Metal</b>	1	ODOT Three-Tube Railing	No modification necessary
	2	ODOT Two-Tube Railing	No modification necessary
	3	ODOT Two-Tube Railing	No modification necessary
	4	Caltrans Concrete Barrier Type 90	No modification necessary
	5 (Galvanized Beam)	None	Does not possess historic appearance
	6	ODOT Two-Tube Railing	Metal attachments

**Table 4.1 Continued**

<b>Metal (Continued)</b>	7	None	Does not possess historic appearance
	8	None	Does not possess historic appearance
	9	ODOT Two-Tube Railing	No modification necessary
	10	None	Does not possess historic appearance
	11	None	Does not possess historic appearance
	12	None	Does not possess historic appearance
	13	None	Does not possess historic appearance
	14	ODOT Two-Tube Railing	Metal attachments
<b>Metal and Concrete</b>	1	None	This is a modern railing
	2	None	This is a modern railing
	3	None	Does not possess historic appearance
	4 (F-type w/ Handrail)	None	This is a modern railing
<b>Pedestrian</b>	1	TxDOT PR3	Metal attachments
	2	TxDOT PR3	Metal attachments
	3	TxDOT PR3	Metal attachments
	4	TxDOT PR3	Metal attachments
	5	ODOT Pedestrian Rail	Metal attachments
	6	TxDOT PR3	Metal attachments
	7	ODOT Pedestrian Rail	Metal attachments
	8	None	Special case
<b>Stone</b>	1	TxDOT T221	Formliners
	2	TxDOT T221	Formliners
	3	TxDOT T221	Formliners
	4	TxDOT T221	Formliners
	5	None	Does not possess acceptable geometry
	6	ODOT Concrete Beam and Post	Custom forms and infill

**Table 4.1 Continued**

<b>Timber</b>	1	None	Special case: covered bridge
	2	None	Special case: covered bridge
	3	None	Special case: covered bridge


#### **4.5.1 Reinforced Concrete Railings**

The primary functions of bridge railings are to keep vehicles from driving off the structure and to safely redirect vehicles during an impact with the railing. Therefore, bridge railings are designed to prevent vehicle snagging and to prevent the railing from protruding into a vehicle during an impact (NCHRP 1993). The vehicle redirection features of the Oregon Department of Transportation (ODOT) concrete beam and post railing were investigated because of the versatility of its shape as well as its crash-resistant geometry. A cross-section of the ODOT concrete beam and post railing is shown in Figure 4.5(a). The railing has a 9-in. high parapet curb for stopping the advance of tires and a 12-in. beam for stopping the advance of bumpers. The parapet curb and the beam of the ODOT concrete beam and post railing are the vehicle-redirecting features of this railing.

The region between the curb and the beam provides strength, but is not part of the vehicle-redirecting features. Therefore, it was considered that railing geometry in this zone can be adjusted with limitations. First, an alteration in shape cannot protrude outside of the original cross-section in this zone. Second, the structural geometry of the approved railing cannot be reduced. Third, the reinforcement cannot be modified to reduce its capacity.

The concrete in this zone between the curb and beam was termed the “workable zone” which allowed for adjustments in geometry such that the geometry of historical railings could be approximated.

To approximate reinforced concrete historical bridge railings, the geometry of two approved railings was considered. These include the ODOT concrete beam and post and the TxDOT T221. Both are TL-4 rated which allow for use on essentially all historic bridges in the state. Figure 4.5 illustrates the workable zone for both railings. The ODOT concrete beam and post and the TxDOT T221 railings serve as the base form from which to replicate or approximate several historic railings (Table 4.2).



(a) ODOT concrete beam and post


(b) TxDOT T221

Figure 4.5 – Workable zone of a reinforced concrete railing

#### 4.5.1.1 TxDOT T221 Railing

The TxDOT T221 was the basis for 17 of the 42 simulated railings (Table 4.2). The TxDOT T221 is a favorable baseline for modification because it possesses a simple geometry as shown in Figure 4.6 and is a crash-tested TL-4 railing. Therefore, this railing can be easily utilized and mobilized in a wide range of scenarios.

There are two primary approaches used to modify this railing. The first is through the use of formwork within the workable zone, and the second is through the use of formliners.



**Figure 4.6 – Cross-section of the TxDOT T221 railing (TxDOT 2014)**

#### 4.5.1.1.1 Approximation with Custom Formwork

A bridge with the Concrete 1 (Bush-Hammered Panel) railing is shown in Figure 4.7. A cross-section of an original Bush-Hammered Panel, taken from a 1937 drawing by the State Highway Commission of Indiana, is shown in Figure 4.8. This railing does not satisfy modern crash test standards; however, it is possible to develop a modification of the TxDOT T221 railing to approximate the same appearance.



(a) Oblique view of bridge

(b) Close-up of railing

Figure 4.7 – Historic bridge with a Bush-Hammered Panel railing






Figure 4.8 – Cross-section of the Bush-Hammered Panel railing



To maintain the appearance of the Bush-Hammered Panel railing and maintain the crash test acceptability of the T221, the T221 railing's cross-section was expanded to accommodate the sunk-in panels of the Bush-Hammered Panel railing, as shown in Figure 4.9. An elevation view is provided in Figure 4.10. There are three key features of the approximated railing. First, the retrofit Bush-Hammered Panel cross-section is sized such that it contains the full size and strength of the T221 railing. Second, the size and location of the reinforcement of the T221 railing were not altered. Third, the sunk-in panels of the new Bush-Hammered Panel railing are contained entirely within the workable zone to provide appropriate crash geometry.




**Figure 4.9 – Cross-section of a retrofit Bush-Hammered Panel railing**




**Figure 4.10 – Elevation view of the retrofit Bush-Hammered Panel railing**

A rendering of the retrofit Bush-Hammered Panel railing is shown in Figures 4.11 and 4.12 on a historic concrete arch bridge. It is important to note that the new Bush-Hammered Panel is an approximation of the original. The geometric characteristics of the workable zone limit the degree to which the original railing can be approximated in the interest of the safety of the impacting vehicle. A similar approach was used to construct approximations of 21 other historic reinforced concrete railings as outlined in Table 4.1.



**Figure 4.11 – Retrofit Bush-Hammered Panel on a historic concrete arch bridge**



**Figure 4.12 – Close-up view of the retrofit Bush-Hammered Panel railing**




#### 4.5.1.1.2 Approximation with Formliners

Standard production formliners can be used in conjunction with the TxDOT T221 railing to approximate a number of railings, including Stone 1 (Figure 4.13), Stone 2 (Figure 4.14), Stone 3 (Figure 4.15), and Stone 4 (Figure 4.16). As an example, Custom Rock produces a variety of formliners, three of which can be used to approximate a historic railing as listed in Table 4.2. Railing texture is created by the formliners while railing color, through the use of concrete stains or color added to the concrete mix, can be provided to enhance the appearance of the railing.

**Table 4.2 – Historic railings and approximating Custom Rock formliners**

<b>Historic Railing</b>	<b>Custom Rock Formliner Name</b>
Stone 1	Yosemite Stone
Stone 2	New England Drystack
Stone 3	New England Drystack
Stone 4	Tollway Ashlar

Relief is a unique characteristic of every formliner. The relief of a formliner is the formliner's maximum depth, and the relief of a particular formliner was accounted for when the simulated historic railings were designed. As shown in Figure 4.9, the size and shape of the cross-section of the base railing (TxDOT T221) is an absolute minimum that cannot be infringed upon.





(a) Railing Detail

(b) Formliner: "Tollway Ashlar"


Figure 4.16 – Stone 4 railing

#### 4.5.1.2 ODOT Concrete Beam and Post Railing

The ODOT concrete beam and post was the basis for 9 of the 42 simulated railings. Figure 4.17 shows a cross-section of the ODOT concrete beam and post railing. The concrete beam and post is a favorable baseline for modification because a variety of geometries can be constructed in its openings. The openings can also be filled to create a different appearance. Similar to the TxDOT T221, the concrete beam and post is a TL-4 railing, making it acceptable in low speed (45 mph or lower) or high speed (50 mph or higher) applications.

To provide an example of the use of the ODOT concrete beam and post railing, it can be modified to approximate the appearance of the railing shown in Figure 4.18. Figure 4.19(a) shows the ODOT concrete beam and post railing in its standard configuration, and Figure 4.19(b) shows it in its modified configuration. The arched openings of the Concrete 11 railing were recreated in the openings of the concrete beam and post. This modification does not reduce the structural strength of the railing or influence its crash resistance geometry.







**Figure 4.17 – Cross-section of the concrete beam and post railing (ODOT 2014)**



**Figure 4.18 – Concrete 11 railing**



**(a) Base railing**




**(b) Simulated historic railing**

**Figure 4.19 – ODOT concrete beam and post modified to approximate Concrete 11**

#### **4.5.2 Metal Tube Railings**

Metal tube railings are very useful for use as base railings, especially for use on historic truss bridges. Metal attachments can be added to the back sides of the tubes to recreate 6 historic railings (Table 4.1). Both the two- and three-tube ODOT metal railings were selected for use. While both railings are rated as TL-4, the two-tube railing is 32.5 in. tall while the three-tube railing is 42 in. tall. Figure 4.20 compares the cross-sections of the different tube configurations.



**Figure 4.20 – ODOT metal tube railing cross-sections (ODOT 2014)**

The metal thru truss shown in Figure 4.21 carries State Road 11 across the East Fork White River in Jackson County, Indiana. The bridge has the Metal 5 (Galvanized Beam) railing type, a railing type which is not desired to replicate because it is neither sturdy enough to withstand an impact nor exemplary of a historic look. Metal thru truss bridges with railings such as the one shown in Figure 4.21 are strong candidates for use of a modified metal tube railing.

A similar metal thru truss bridge that still possesses its original railing is shown in Figure 4.22. The light green Metal 14 railing shown is a historically-accurate railing for a metal thru truss and can be approximated as shown in Figure 4.23. In this manner, the Galvanized Beam railing used on the bridge in Figure 4.21 can be replaced with a more aesthetic railing, improving safety in the process.






**Figure 4.21 – Metal thru truss with a railing ineligible for replication**



**Figure 4.22 – Close-up of Metal 14 railing (light green)**




**Figure 4.23 – Modified ODOT two-tube railing on a metal thru truss**

Another retrofit is shown in Figures 4.24 and 4.25. The Metal 6 railing on the pony truss bridge shown in Figure 4.24 is characterized by metal strips arranged in a lattice pattern. Metal attachments can be added to the ODOT two-tube railing to match the appearance of a historic Metal 6 railing. This solution is desirable because it removes the railing from the truss members while also improving the overall aesthetics of the bridge.



**Figure 4.24 – Metal 6 railing on historic pony truss bridge**




**Figure 4.25 – Modified ODOT two-tube railing**

### 4.5.3 Pedestrian Railings

Pedestrian railings are subject to different requirements than traffic railings. Section 13.8 of the AASHTO *LRFD Bridge Design Specifications 7<sup>th</sup> Ed.* contains the design requirements for pedestrian railings (AASHTO 2014). In general, all pedestrian railings must be at least 42 in. tall. The openings in a pedestrian railing must be proportioned such that a 6 in. diameter sphere cannot pass through an opening in the lower 27 in. of the railing and that an 8 in. diameter sphere cannot pass through an opening above the lower 27 in. of the railing. Furthermore, if a chain-link fence is used in a pedestrian railing, the openings of the mesh cannot exceed 2 in.

Contrary to traffic railings, pedestrian railings do not require crash testing; however, AASHTO still prescribes design forces. The design live load for a pedestrian railing is 50 lb/ft, acting horizontally and vertically on each longitudinal element of a railing, as shown in Figure 4.26. Additionally, a concentrated load of 200 lb is applied to a longitudinal element at any point in any direction, acting simultaneously with the distributed live load. Finally, the posts of pedestrian railings must be designed for a transverse concentrated load of at least 200 lb applied at the center of gravity of the upper longitudinal element or at a height of 5 ft, whichever is smaller (AASHTO 2014).







**Figure 4.26 – Application of distributed load on a pedestrian railing (AASHTO 2014)**

Because pedestrian railings do not require crash testing, nearly perfect approximations of seven of the eight found in Indiana were possible (Pedestrian 1 through 7). The Pedestrian 8 railing was observed on only one bridge, a bascule bridge in LaPorte County. The bridge's counter-weights may have to be adjusted if a new railing is installed. For this reason, Pedestrian 8 is considered a special case and it was not replicated.

The seven approximated pedestrian railings are loosely based on either the Texas Department of Transportation (TxDOT) PR3 railing (Figure 4.27) or the Oregon Department of Transportation (ODOT) Pedestrian Rail (Figure 4.28). Standard drawings of the pedestrian railings are shown in Appendix A, and photographs of the pedestrian railings are provided in Appendix D. Drawings of the simulated modern pedestrian railings are shown in Appendix E.



**Figure 4.27 – Rendering of the TxDOT PR3 railing**



**Figure 4.28 – Rendering of the ODOT Pedestrian Rail**

#### **4.5.4 Summary of Design Methodology**

The methodology for the development of a simulated historic railing is as follows:

1. Select a modern crash-tested traffic railing or pedestrian railing to serve as a baseline. These include TxDOT PR3, TxDOT T221, ODOT concrete beam and post, ODOT two-tube curb-mounted, ODOT pedestrian, and the INDOT FC.

2. Expand the cross-section, leave the reinforcement details exactly the same, and make desired geometric modifications in the “workable zone” (reinforced concrete railing) or add non-structural attachments (metal tube railing).
3. Develop drawings and renderings of the simulated historic railing. Because the cross-sections were expanded and the reinforcement was not altered, railing strength is considered to be adequate. This overall approach can be used to simulate any historic railing. The majority of railings used in Indiana were designed and are included in Appendix D (renderings) and Appendix E (design drawings).

#### **4.6 Retrofit Selection Procedure**

Figure 4.29 presents a visual guide to the process of selecting a retrofit. Orange boxes contain solution strategies. A distinction is made between TL-2 railings and TL-4 railings because the Washington D.C. curb railing is only applicable on bridges for which a TL-2 railing is appropriate.




Figure 4.29 – Flowchart for selecting a retrofit strategy



## CHAPTER 5. SUMMARY AND CONCLUSION

### 5.1 Summary

In July 2006, the Indiana Department of Transportation (INDOT) began a programmatic agreement with the Federal Highway Administration (FHWA) to manage and maintain its historic bridges. This agreement signaled the beginning of Indiana's effort to preserve its historic bridges. As of January 2014, 658 historic bridges remain in service in Indiana. Preserving these historic bridges is important especially considering the rich cultural icons that these bridges represent.

Most of the 658 historic bridges in the state have railings that do not meet current strength and safety standards. The objective of this study was to develop strategies that can be used to address existing railings on historic bridges and to develop solutions that meet current design requirements. Previous research has focused on developing retrofit railings through rigorous design and crash-testing programs. Moreover, previous research has focused on developing railings for specific bridges. These methods were not preferred for use in Indiana due to the variety and range of historic bridges in the state's inventory.

## **5.2 Conclusions**

Indiana is among 19 states that have a programmatic agreement to manage its historic bridges. Indiana's historic bridge inventory was investigated to determine how many historic bridges remain in service as well as to document the types and variety of historic railings in existence. As of January 2014, 658 historic bridges remain in service in Indiana. On these 658 historic bridges, 61 different historic railings were identified. Of these, 7 railing types, along with bridges with no railing, constitute 2/3 of the entire inventory. It is interesting that 25 of the other railings occur on only one single bridge and 11 of the other railings occur on only two bridges. Therefore, 59% of the different railing types are unique. Based on this analysis, research focused on addressing the most common railings identified. However, an attempt was also made to address as many of the unique railings as possible.

Three different options utilizing modern, previously crash tested railings were identified to upgrade the railings on Indiana's historic bridges. The first option is to install a modern railing inside of the original railing. When this option is exercised, the original railing may remain on a bridge. The second option is to install a special inboard railing on the curb. This special railing, which can be used if the bridge has a sidewalk, protects pedestrians on the sidewalk and allows the original railing to be retained. The third option is railing replacement. A collection of approved, crash-tested railings developed by a number of states was used as a baseline to design simulated railings to approximate the appearance of historic railings.

Simulated railings were developed to cover a variety of historic concrete and steel railings. These railings maintained the overall structure and crash resistant geometry of the base railing while integrating geometric features of the historic railing. In all, it was possible to simulate 42 of the historic railings existing in Indiana. These railings cover 66.3% of all historic bridges in the state. Three timber railing types, which were not considered in the scope of this research, accounted for 8.4% of all historic bridges in the state. Sixteen railing types did not possess a historic look, did not possess acceptable geometry, or did not exemplify historic craftsmanship. These railings accounted for 25% of all historic bridges in the state.

Through the use of strategies developed in this research, it is possible to retain historic railing appearance of the majority of historic bridges in Indiana. In many cases, it is also possible to improve aesthetics. More importantly, however, these strategies allow for improvement in the safety of the traveling public.

## REFERENCES

## REFERENCES

- AASHTO (2014), *LRFD Bridge Design Specifications, 7<sup>th</sup> Ed*, American Association of State Highway and Transportation Officials, Washington, D.C.
- AASHTO (1994), *LRFD Bridge Design Specifications, 1<sup>st</sup> Ed*, American Association of State Highway and Transportation Officials, Washington, D.C.
- AASHTO (2009), *Manual for Assessing Safety Hardware*, American Association of State Highway and Transportation Officials, Washington, D.C.
- AASHTO (2008), *Guidelines for Historic Bridge Rehabilitation and Replacement*, American Association of State Highway and Transportation Officials, Washington, D.C.
- Barker, R. M. and Puckett, J.A. (2013), *Design of Highway Bridges: An LRFD Approach*, John Wiley & Sons, Inc. Hoboken, NJ, 528 pp.
- Buth, C. Eugene (2004), *Truss Bridge Retrofit Railings*, Texas Transportation Institute, College Station, TX, 4 pp.
- Buth, C. Eugene; Haug, Rebecca R.; Menges, Wanda L.; and Williams, William F. (2004), *Retrofit Railings for Truss Bridges*, Texas Transportation Institute, College Station, TX, 258 pp.
- Caltrans, *Bridge Rails and Barriers*, California Department of Transportation, [http://www.dot.ca.gov/hq/LandArch/barrier\\_aesthetics/Caltrans\\_Bridge\\_Rails\\_and\\_Barriers.pdf](http://www.dot.ca.gov/hq/LandArch/barrier_aesthetics/Caltrans_Bridge_Rails_and_Barriers.pdf) (accessed May 29, 2014).
- Carver, Martha (2008), *Tennessee's Survey Report for Historic Highway Bridges*, Tennessee Department of Transportation, Nashville, TN. 643 pp.
- Custom Rock Formliner, *New England Drystack*, Custom Rock Formliner, <http://www.customrock.com/pattern/new-england-drystack/> (accessed July 27, 2014)
- Custom Rock Formliner, *Tollway Ashlar*, Custom Rock Formliner, <http://www.customrock.com/pattern/tollway-ashlar/> (accessed July 27, 2014).

- Custom Rock Formliner. *Yosemite Stone*, Custom Rock Formliner, <http://www.customrock.com/pattern/1120d-yosemite-stone/> (accessed July 27, 2014).
- FHWA, *Federal Highway Administration*, The U. S. Department of Transportation (USDOT) and the Federal Highway Administration (FHWA), <http://www.fhwa.dot.gov/> (accessed July 31, 2014).
- FHWA (2014), *Bridge Railings*, Federal Highway Administration, [http://safety.fhwa.dot.gov/roadway\\_dept/policy\\_guide/road\\_hardware/barriers/bri\\_dgerailings/](http://safety.fhwa.dot.gov/roadway_dept/policy_guide/road_hardware/barriers/bri_dgerailings/) (accessed July 31, 2014).
- Google Street View, *353 State Hwy 16, Llano, Texas*, Google, <https://www.google.com/maps/@30.753385,-98.675765,3a,75y,155.24h,90t/data=!3m4!1e1!3m2!1sIXUqLqgEBxn182YK77qLiA!2e0> (accessed December 1, 2014).
- INDOT, *English Section 700*, Indiana Department of Transportation, <http://www.in.gov/dot/div/contracts/standards/drawings/sep12/e/sep700.htm> (accessed Sept. 18, 2014).
- INDOT, *Historic Bridges Inventory Summary & Results*, Indiana Department of Transportation, <http://www.in.gov/indot/2531.htm> (accessed July 31, 2014).
- INDOT (2013), *Indiana Design Manual*. Indiana Department of Transportation, Indianapolis, Indiana.
- INDOT (2006), *Programmatic Agreement Regarding Management and Preservation of Indiana's Historic Bridges*. Indiana Department of Transportation, Indianapolis, IN, 11 pp.
- Mead & Hunt (2012), *Historic Bridge Practices Nationwide: Inventory, Evaluation, and Management*, Mead & Hunt, 4 pp.
- NPS, *National Park Service*, The U.S. Department of the Interior and the National Park Service (NPS), <http://www.nps.gov/nr/> (accessed July 31, 2014)
- NCHRP (1993), *Report 350: Recommended Procedures for the Safety Performance Evaluation of Highway Features*. Transportation Research Board, Washington, D.C., 64 pp.
- NCHRP (1999), *Synthesis 275: Historic Highway Bridge Preservation Practices*. Transportation Research Board, Washington, D.C. 58 pp.

- O'Connell, Lenahan; Grossardt, Ted; Ripy, John (2013), *Assessment of Kentucky's Historic Truss Bridges*, Kentucky Transportation Center, Lexington, KY. 184 pp.
- ODOT (2007), *Historic Bridge Preservation Plan*. Oregon Department of Transportation, Salem, Oregon, 30 pp.
- ODOT, *Bridge Standards Unit*, Oregon Department of Transportation, [http://www.oregon.gov/odot/hwy/bridge/Pages/standards\\_manuals.aspx](http://www.oregon.gov/odot/hwy/bridge/Pages/standards_manuals.aspx) (accessed Nov. 10, 2014).
- Parsons Brinckerhoff (2012), *Best Practices and Lessons Learned on the Preservation and Rehabilitation of Historic Bridges*, Parsons Brinckerhoff, Washington, D.C. 129 pp.
- TxDOT (2012), *Bridge Railing Manual*. Texas Department of Transportation, Austin, TX, 61 pp.
- TxDOT, *Bridge Standards (English)*, Texas Department of Transportation, <https://www.dot.state.tx.us/insdtdot/orgchart/cmd/cserve/standard/bridge-e.htm> (accessed May 29, 2014).
- TxDOT (2010), *Historic Bridge Manual*. Texas Department of Transportation, Austin, TX, 40 pp.
- TranSystems (2010), *Ohio Historic Bridge Maintenance & Preservation Guidance*, TranSystems, Kansas City, MO. 48 pp.
- Williams, William (2010), "Structural Analyses, Design, and Testing of Retrofit Bridge Rail," *Journal of the Transportation Research Board*, Transportation Research Board of the National Academies, Washington, D.C., pp 47-55.
- Wright Jr., Frederick G, "INFORMATION: Bridge Rail Analysis," Memo to Resource Center Directors and Division Administrators, Federal Highway Administration, [http://safety.fhwa.dot.gov/roadway\\_dept/policy\\_guide/road\\_hardware/barriers/bridgerailings/](http://safety.fhwa.dot.gov/roadway_dept/policy_guide/road_hardware/barriers/bridgerailings/) (accessed May 16, 2000).

## **APPENDICES**




## APPENDIX A. MODERN RAILING STANDARD DRAWINGS

Standard drawings are provided for a variety of crash-tested railings. Table A.1 lists the railings included along with their Test Levels.

**Table A.1 – List of standard drawings provided**


<b>State DOT</b>	<b>Railing ID</b>	<b>Test Level</b>	<b>Pages</b>
TxDOT	T411	2	74 – 75
TxDOT	C411	2	76 – 78
TxDOT	C412	4	79 – 82
INDOT	TX	2	83 – 86
TxDOT	T221	4	87 – 88
ODOT	Concrete Beam and Post	4	89
INDOT	FC	4	90 – 91
ODOT	Two-Tube Railing	4	92 – 93
ODOT	Three-Tube Railing	4	94 – 95
Caltrans	Type 90	4	96 – 98
TxDOT	PR3	N/A	99 – 100
ODOT	Pedestrian Rail	N/A	101
DDOT	Washington, D.C. Curb Railing	2	102






EXTERIOR PILASTER ELEVATIONS

- ① Provide rail joints at ends of all spans the same width as Slab joint opening, except that Rail joints over construction joints must be  $\frac{1}{4}$ " Min to  $\frac{3}{8}$ " Max in width. Joints must be open. If slab joint opening is not sealed, joints over construction joints and over sealed deck joints must be plugged. Forming material used in joints may be left in place if it is light in color and compressible, such as the following materials: polystyrene, molded cork granules, sponge rubber sheet, etc. If forming material is not left in place, the bottom 6" must be plugged with slab joint sealing compound to prevent drainage and staining.
- ② Increase 2" for structures with overlay.
- ③ Construction year (use if shown elsewhere on plans) 3" High "Platin Bold" Typeface with  $\frac{1}{4}$ " recess. Placed at one Abutment only or as directed by the Engineer.
- ④ Dimensions must be the same on each side of joint.
- ⑤ Reduce by 2" or field bend over Preformed Bituminous Fiber Material to gain cover.
- ⑥  $5\frac{1}{2}$ " when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑦ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars must be furnished at the Contractor's expense.
- ⑧ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑨ Bronze Star dimensions of the final product can be slightly smaller due to shrinkage after casting.




ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS



SECTION THRU POST ON BRIDGE SLAB (Showing Pilaster)

SECTIONS THRU RAIL



BRONZE STAR DETAIL


- Two known manufacturers are:
1. Kassone Castings Austin, Texas
  2. Southwell Company San Antonio, Texas

TYPE A

TYPE B

TYPE C

WINDOW TYPES



#### CONSTRUCTION NOTES:

Attach Bronze Star with a Type III Class C epoxy. Clamp star until epoxy achieves set. Remove any visible epoxy "squeeze out" from under star. Face of rail and pilasters, parapet must be plumb unless otherwise approved by the Engineer. A one rub finish must be applied to all railing surfaces unless otherwise shown elsewhere on the plans.

#### MATERIAL NOTES:

All concrete for railing wall must be Class "C". Provide Class "C" (HPC) concrete if shown elsewhere in the plans. All reinforcing must be Grade 60. Epoxy coat all rail reinforcement if slab bars are epoxy coated. Bronze Star must be cast of architectural bronze having the following composition: Copper 85 %, Tin 5 %, Lead 5 %, Zinc 5 %.

#### GENERAL NOTES:

This rail was evaluated based on the results of previous crash tests and approved for a NCHRP Report 350 TL-2 rating. This rail is only approved for low speed use, design speeds of 45 mph and less.

This railing cannot be used on bridges with expansion joints providing more than 5" movement.

Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.

Shop drawings will not be required for this rail. See Bridge Layout or other plan sheets for the following dimensions with the number of span pilasters, dimensions with the number of windows, window type, inclusion of bronze stars, inclusion of construction year with abutment identity.

Erection drawings showing span number, span pilaster locations, number of windows between pilasters and spacing to first window (see Note 6) must be submitted to the Engineer for approval.

Average weight of railing with no overlay increase and no pilasters is 270 plf.

SHEET 2 OF 2




Texas Department of Transportation  
Bridge Division

TRAFFIC RAIL  
TEXAS CLASSIC

TYPE T411




FILE	FILED	DATE	BY	DATE	BY	DATE	BY
11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011
11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011
11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011
11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011	11/14/2011





### SECTIONS THRU RAIL WITHOUT RAISED SIDEWALK

- ⑨ Increase 2" for structures with overlay.
- ⑩ 5 1/2" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑪ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars must be furnished at the Contractor's expense.
- ⑫ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑬ Raised Sidewalk



### SECTIONS THRU RAIL WITH RAISED SIDEWALK


SHEET 2 OF 3

Texas Department of Transportation  
Bridge Division


COMBINATION RAIL  
TEXAS CLASSIC

TYPE C411



DESIGN	1/10/2011 dgp	REV	1/10/2011 dgp	REV	1/10/2011 dgp	REV	1/10/2011 dgp
DATE	1/10/2011	REV	1/10/2011	REV	1/10/2011	REV	1/10/2011
DESIGN	1/10/2011	REV	1/10/2011	REV	1/10/2011	REV	1/10/2011
DESIGN	1/10/2011	REV	1/10/2011	REV	1/10/2011	REV	1/10/2011
DESIGN	1/10/2011	REV	1/10/2011	REV	1/10/2011	REV	1/10/2011



EXTERIOR PILASTER ELEVATIONS  
(Showing without raised sidewalk)



WINDOW TYPES  
TYPE A TYPE B TYPE C



BRONZE STAR DETAIL<sup>23</sup>

- Two known manufacturers are:  
1. Kasson Castings  
Austin, Texas  
2. Southwell Company  
San Antonio, Texas

- ① Provide roll joints at ends of all spans the same width as Slab joint opening, except that Roll joints over construction joints must be 1/4" Min to 3/4" Max in width. Joints must be open. If slab joint opening is not sealed, joints over construction joints and over sealed deck joints must be plugged. Forming material used in joints may be left in place if it is light in color and compressible, such as the following materials: polystyrene, rolled cork granules, sponge rubber sheet, etc. If forming material is not left in place, the bottom 6" must be plugged with slab joint sealing compound to prevent drainage and staining.
- ② Increase 2" for structures with overlay.
- ③ Construction year (use if shown elsewhere on plans) 3" High "Platin Bold" Typeface with 1/4" recess. Placed at one Abutment only or as directed by the Engineer.
- ④ Dimensions must be the same on each side of joint.
- ⑤ For raised sidewalks, add sidewalk height to total bar height. Use sidewalk height at rail's location.
- ⑥ Reduce by 2" or field bend over Preformed Bituminous Fiber Material to gain cover.
- ⑦ Bronze Star dimensions of the final product can be slightly smaller due to shrinkage after casting.

#### CONSTRUCTION NOTES:

Attach Bronze Star with a Type III Class C epoxy. Clamp star until epoxy achieves set. Remove any visible epoxy "squeeze out" from under star.  
Face of rail and pilasters, parapet must be plumb unless otherwise approved by the Engineer.  
A one rub finish must be applied to all railing surfaces unless otherwise shown elsewhere on the plans.

#### MATERIAL NOTES:

All concrete for rolling wall must be Class "C". Provide Class "C" (HPC) concrete if shown elsewhere in the plans.  
All reinforcing must be Grade 60.  
Epoxy coat all rail reinforcement if slab bars are epoxy coated.  
Bronze Star must be cast of architectural bronze having the following composition: Copper 85 %, Tin 5 %, Lead 5 %, Zinc 5 %.

#### GENERAL NOTES:

This roll was evaluated based on the results of previous crash tests and approved for a NCHRP Report 350 TL-2 rating. This roll is only approved for low speed use, design speeds of 45 mph and less.  
This rolling cannot be used on bridges with expansion joints providing more than 3" movement.  
Roll anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.  
Shop drawings will not be required for this roll.  
See Bridge Layout or other plan sheets for the following dimensions with the number of span pilasters, dimensions with the number of windows, window type, inclusion of bronze stars, inclusion of construction year with abutment identity.  
Erection drawings showing span number, span pilaster locations, number of windows between pilasters and spacing to first window (see Note 6) must be submitted to the Engineer for approval.  
Average weight of railing with no overlay increase and no pilasters is 350 pcf.



SHEET 3 OF 3

Texas Department of Transportation  
Bridge Division


COMBINATION RAIL  
TEXAS CLASSIC

TYPE C411

PLAN: F140001.dgn	DATE: 04/11/2009	DESIGN: 04/11/2009	REVISION: 04/11/2009	DATE: 04/11/2009
STATUS: 04/11/2009	DESIGN: 04/11/2009	REVISION: 04/11/2009	DATE: 04/11/2009	DATE: 04/11/2009
NO. 0000	NO. 0000	NO. 0000	NO. 0000	NO. 0000
NO. 0000	NO. 0000	NO. 0000	NO. 0000	NO. 0000



**INTERMEDIATE WALL JOINT DETAIL**  
(Showing without raised sidewalk)  
Provide at all interior bents without slab expansion joints. Space equally in between at 33' Max, 10' Min.



- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Metal Beam Guard Fence Transitions must be attached to the bridge rail and extended along the embankment unless otherwise shown in the plans.
- ② Increase 2" for structures with overlay.
- ③ Wingwall length minus 4'-2" (variable) 10' Min.

SHEET 1 OF 4

Texas Department of Transportation  
Bridge Division

**COMBINATION RAIL**






**TYPE C412**

PLAN	11/4/2015-5/1/11	REV	1/2/11	REV	1/2/11
DATE	11/4/2015	REV	1/2/11	REV	1/2/11
DESIGNED		CHECKED		APPROVED	
BY		DATE		DATE	













**SECTIONS THRU RAIL WITHOUT RAISED SIDEWALK**  
(Reveals not shown for clarity. See "Typical Reveal Location Detail".)



**SECTIONS THRU RAIL WITH RAISED SIDEWALK**  
(Reveals not shown for clarity. See "Typical Reveal Location Detail".)



- ② Increase 2" for structures with overlay.
- ③ Wingwall length minus 4'-2" (variable) 10' Min.
- ⑤ 5 1/2" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑥ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑦ Raised Sidewalk.

SHEET 3 OF 4

**COMBINATION RAIL**

**TYPE C412**

FILE: C412(1).dgn	ON: TxDOT	BY: TxDOT	DATE: 01/01/01	REV: 01								
PROJECT: 01-001	SECTION: 01-001	PROJECT: 01-001	SECTION: 01-001	REV: 01								
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>DATE: 01-01-01</td> <td>DATE: 01-01-01</td> <td>DATE: 01-01-01</td> <td>DATE: 01-01-01</td> </tr> <tr> <td>DATE: 01-01-01</td> <td>DATE: 01-01-01</td> <td>DATE: 01-01-01</td> <td>DATE: 01-01-01</td> </tr> </table>					DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01
DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01									
DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01	DATE: 01-01-01									









- ② Increase 2" for structures with overlay.
- ⑧ For raised sidewalks, add sidewalk height to total bar height. Use sidewalk height at rail's location.

**CONSTRUCTION NOTES:**  
The back of rolling must be vertical unless otherwise shown on the plans or approved by the Engineer.


**MATERIAL NOTES:**  
All steel components except reinforcing must be galvanized unless otherwise shown on plans. Use Class "C" concrete. Use Class "C" (HPC) if required elsewhere.  
All reinforcing steel must be Grade 60.  
Epoxy coat all reinforcement if slab bars are epoxy coated.

**GENERAL NOTES:**  
This roll has been successfully evaluated by full-scale crash test to meet NCRR Report 300 TL-4 criteria. This roll can be used for design speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this roll can only be used for design speeds of 45 mph and less.  
This rolling cannot be used on bridges with expansion joints providing more than 5" movement. Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.  
Shop drawings are not required for this roll.  
Average weight of rolling with no overlay is 560 pcf.



SHEET 4 OF 4

COMBINATION RAIL							
TYPE C412							
DATE: 11/08/2011	BY: T. D. T. / J. B.	DATE: 11/08/2011	BY: T. D. T. / J. B.	DATE: 11/08/2011	BY: T. D. T. / J. B.	DATE: 11/08/2011	BY: T. D. T. / J. B.
DESIGNER:		CHECKER:		APPROVER:		DATE:	
REVISIONS:		COUNT:		REVISION:		DATE:	
BY: T. D. T. / J. B.		COUNT:		REVISION:		DATE:	



#### NOTES

1. See Standard Drawing E 706-BRTX-02, -03, and -04 for sections.
2. Select the number of windows and adjust dimension X to fit the span length.
3. Span pilasters may be omitted for a short span with  $X \leq 2'-0"$ .
4. Span pilasters are for aesthetic purposes only. Omitting span pilasters does not decrease the integrity of the railing.
5. Dimension  $a = 2X + 3' 1/2"$ . Space bars within dimension  $a$  equally  $\leq 6"$ .
6. See Standard Drawing E 706-TTXX-01 for Concrete Bridge Railing Transition, TTXX.
7. All reinforcing bars designated E shall be epoxy coated.
8. Window opening. See Standard Drawing E 706-BRTX-02 for details.
9. See Standard Drawing E 706-BRTX-03 for span pilaster details.
10. See Standard Drawing E 706-BRTX-04 for pier and end bent pilaster details.

#### INDIANA DEPARTMENT OF TRANSPORTATION

#### RAILING, TX TYPICAL PANEL


SEPTEMBER 2012

STANDARD DRAWING NO. E 706-BRTX-01




/s/ Richard L. VanCleave 09/04/12  
SUPERVISOR, ROADWAY STANDARDS DATE

/s/ Mark A. Miller 09/04/12  
CHIEF ENGINEER DATE



#### NOTES

1. All reinforcing bars designated E shall be epoxy coated.
2. All chamfered edges shall be 3/4".
3. See Standard Drawing E 706-BRTX-04 for reinforcing-bar diagrams.
4. Construction joint type A. See Standard Drawing E 702-CITA-01 for details.




SECTION D-D

#### INDIANA DEPARTMENT OF TRANSPORTATION

#### RAILING, TX WINDOW DETAILS





SEPTEMBER 2012

STANDARD DRAWING NO. E 706-BRTX-02



/s/ Richard L. VanCleave 09/04/12  
SUPERVISOR, ROADWAY STANDARDS DATE

/s/ Mark A. Miller 09/04/12  
CHIEF ENGINEER DATE



#### NOTES


1. All reinforcing bars designated E shall be epoxy coated.
2. All chamfered edges shall be 3/4".
3. See Standard Drawing E 706-BRTX-04 for reinforcing-bar diagrams.
- ④ Construction joint type A. See Standard Drawing E 702-CJTA-01 for details.
- ⑤ Adjust dimension X to fit the span length, depending upon the number of window openings.

INDIANA DEPARTMENT OF TRANSPORTATION


RAILING, TX  
SPAN PILASTER

SEPTEMBER 2012


STANDARD DRAWING NO. E 706-BRTX-03




/s/ Richard L. VanCleave	09/04/12
SUPERVISOR, ROADWAY STANDARDS	DATE
/s/ Mark A. Miller	09/04/12
CHIEF ENGINEER	DATE



ELEVATION




SECTION H-H




SECTION I-I

NOTES


1. All reinforcing bars designated E shall be epoxy coated.
2. See Standard Drawing E 703-BRST-01 for reinforcing-bar bending details and notes.
3. All chamfered edges shall be 3/4".
- ④ Construction joint type A. See Standard Drawing E 702-CJTA-01 for details.



S700E x 8'-10"



S702E x 2'-2"




#7E BENT BAR x (X + 2'-6")

INDIANA DEPARTMENT OF TRANSPORTATION

RAILING, TX  
PIER OR END BENT PILASTER


SEPTEMBER 2012

STANDARD DRAWING NO. E 706-BRTX-04




/s/ Richard L. VanCleave 09/04/12  
SUPERVISOR, ROADWAY STANDARDS DATE

/s/ Mark A. Miller 09/04/12  
CHIEF ENGINEER DATE



Provide at all interior bents without slab expansion joints. Space equally in between at 33' Max, 10' Min.


AT INTERMEDIATE  
WALL JOINTS



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT

## SHEET 1 OF 2



 Texas Department of Transportation  
Bridge Division


TYPE T221


FILE#	rist0004.dgn	DR1 TxDOT	CR1 TxDOT	DR1 JTR	CR1 TxDOT
① TxDOT	april 2009	DEVELOP	FEDERAL AID PROJECT		
RD-00000					
CR-1:	will delete notes.				
CR-2	Standard Transition	COUNTY	CONTROL	SEC	JOB

- ① Terminal Connectors and associated hardware are to be paid for under the item "Metal Beam Guard Fence". Metal Beam Guard Fence Transitions must be attached to the Bridge rail and extended along the embankment until all structural steel is covered.
- ② Back of roll offset may, with Engineer's approval be continued to the end of the railing.
- ③ Increase 2" for structures with overlay.
- ④ Boils must be of sufficient length to extend  $\frac{1}{2}$ " to  $\frac{3}{4}$ " beyond nut.
- ⑤ Bolt recesses are only required when pedestrian sidewalks are adjacent to back of rail.
- ⑥ 4 additional Bars R(4) 3'-8" in length must be placed inside Bars S(4) and centered 2'-0" on each end of rail. All connections are required. Field bend as needed.











QUANTITIES FOR ONE RUNNING FOOT OF RAILING	
Concrete, class C	2.58 CFT
Reinforcing bars	26.3 LBS

#### NOTES

1. See Standard Drawing E 706-BRSF-03 for General Notes.
2. See Standard Drawing E 703-BRST-01 for reinforcing-bar bending details and notes.




INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE RAILING  
TYPE FC



SEPTEMBER 2012

STANDARD DRAWING NO. E 706-BRSF-01



/s/ Richard L. VanCleave 09/04/12  
SUPERVISOR, ROADWAY STANDARDS DATE

/s/ Mark A. Miller 09/04/12  
CHIEF ENGINEER DATE



#### GENERAL NOTES


1. Minimum lap for #5 bars shall be 1'-11".
- (2) Construction joint type A. See Standard Drawing E 702-CJTA-01 for details.
3. A joint shall be provided between the bridge railing and railing transition at the end of the bridge slab as shown on Standard Drawing E 706-CBRT-01.
- (4) For twin structures or other structures which are placed side by side, this dimension shall be reduced to 0 on the median side.
- (5) For twin structures or other structures which are placed side by side, this dimension shall be reduced to 1'-4" on the median side.
6. All reinforcing bars designated E shall be epoxy coated.

#### INDIANA DEPARTMENT OF TRANSPORTATION


#### CONCRETE BRIDGE RAILING PLACEMENT


SEPTEMBER 2012

STANDARD DRAWING NO. E 706-BRSF-03





/s/ Richard L. VanCleave	09/04/12
SUPERVISOR, ROADWAY STANDARDS	DATE
/s/ Mark A. Miller	09/04/12
CHIEF ENGINEER	DATE










NOTE 1:  
Transition posts may be steel W6x9 or timber 8" x 8". All posts to be of same material.  
See dwg. BR203 "Thrie Beam Blockouts"




NOTE:  
For End Panel reinforcement not shown see project plans. For rail and curb details not shown see dwg. BR206.




Accompanied by dwgs. BR203, BR206, RD400, RD405 and RD410

CALC. BOOK NO.	BASLINE/REPORT DATE: 01-JUL-2009
NOTE: All material and workmanship shall be in accordance with the current Oregon Standard Specifications	
OREGON STANDARD DRAWINGS	
2-TUBE CURB MOUNT RAIL TRANSITION	
2008	
DATE	REVISION DESCRIPTION
01-08	Added B1000 in Accompanied by dwgs. and Note 1)
01-11	Changed 24" to 24" x 14" to 14" and 14" to 14" x 14"
The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without consulting a Registered Professional Engineer	


















The image contains four technical drawings for pedestrian rail components:

- END VIEW OF PILASTER:** Shows a cross-section of the pilaster. Key dimensions include a 1'-0" face of rail, 10 1/2" pilaster width, 5 1/4" top of pipe rail, 1 1/2" top of sidewalk, and 6" anchor bars. It also shows a 3/4" chamfer and a 3" minimum dimension.
- PILASTER ELEVATION:** Shows the side view of the pilaster. Key dimensions include a 2'-0" width, 2" bars (#4) at 3" spacing, 1 1/2" end cover, 3/4" chamfer, 6" curb, and 4" anchor bars. It also shows a 3'-7 3/4" length and a 2" minimum dimension.
- PIPE RAIL SECTION:** Shows a cross-section of the pipe rail. Key dimensions include a 3'-0" width, 3/4" end cover, 3" standard pipe cap, 3" standard pipe, 3/4" sq bar, 1'-6" anchor bars, and 3'-7 3/4" length.
- ELEVATION OF TYPICAL CURB REINFORCING:** Shows the side view of the curb. Key dimensions include a 6" width, 4" anchor bars spaced at 2'-0" max, 1 1/2" end cover, 3/4" chamfer, and 6" curb.

ELEVATION OF TYPICAL REINFORCING  
WITH PIPE RAIL AND PILASTER CONNECTION

SHEET 1 OF 2




 Texas Department of Transportation  
Bridge Division

## PEDESTRIAN RAIL

TYPE PR3

FILE: 71800030.dgn	On TxDOT	On TxDOT	On JTR	On JTR
① TxDOT April 2009	DISTRICT	FEDERAL AID PROJECT		TASKET
REVISIONS				
	COUNTY	CONTROL	SECT	JOB
				REMARKS



### PIPE RAIL DETAILS

- ⑧ Pilasters will be plumb on all sides (Typ).
- ⑨ See "General Notes" for anchor bolt information.
- ⑩ Embed (#4) anchor bars 5" with a Type III (Class C) epoxy meeting the requirements of DMS-6100, "Epoxies and Adhesives".
- ⑪ Firmly tighten Self Drilling Screws after pipe rail has been attached to Pilasters.

#### CONSTRUCTION NOTES:


Pilasters must be plumb on all sides. For curved rolling applications, fabricate the rail to the curve if radius is less than 600 ft. Shop drawings are required when rail is fabricated to the curve. Exposed edges of pipe rail and pipe caps must be rounded or chamfered to approximately 1/8" by grinding.

#### MATERIAL NOTES:


Pipe for pipe rail must conform to ASTM A53 Gr B or 4500 Gr B. Steel plates and steel bars must be ASTM A36. Galvanize all steel components except reinforcing steel unless noted otherwise. When the plans require painted steel, follow the requirements for painting galvanized steel in Item 446, "Cleaning and Painting Steel". Reinforcing steel must be Grade 60. Epoxy coat all rail reinforcement except embedded portion of anchor bars if slab bars are epoxy coated. (#4) anchor bar used for the epoxied anchorage system must not be epoxy coated for the embedded portion. Use Class "C" concrete, Use Class "C" (HPC) if required elsewhere. Chamfer all exposed corners. Anchor bolts must be 3/4" Dia ASTM A36 threaded rods with one hex nut and one hardened steel washer at each bolt. Minimum embedment depth of 3/4" Dia threaded rod is 3 1/2". Embed threaded rods into pilasters with a Type III (Class C) epoxy meeting the requirements of DMS-6100, "Epoxies and Adhesives". Anchor installation including hole size, drilling, and clean-out, must be in accordance with manufacturer's instructions.

#### GENERAL NOTES:

Designed according to AASHTO LRFD Specifications. Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications. This railing cannot be used on bridges with expansion joints providing more than 5" movement. Shop drawings are not required unless otherwise noted. For all rails, erection drawings must be submitted to the Engineer for approval to ensure proper installation. Drawings must show pilaster spacing, sleeve pipe cap locations on pilasters, and panel lengths with identification showing where each panel goes on the layout. Average weight of railing: 158 pcf total (136 pcf (conc), 22 pcf (steel)).



### SECTIONS THRU PILASTER



### SECTIONS THRU CURB


SHEET 2 OF 2








Texas Department of Transportation  
Bridge Division

### PEDESTRIAN RAIL

#### TYPE PR3

FILED: 7/18/2009, gpr	ON: 7/20/07	BY: 1/20/07	ON: 2/10/07
7/20/07	April 2009	REVISIONS	DATE
COUNTY	CONTRACT	SHEET	NO.





ALTERNATE ANCHORAGE

\* OFFSET DISTANCE AND LENGTH ARE BASED ON AASHTO ROADSIDE DESIGN GUIDE AND MAY BE ADJUSTED TO ALLOW FOR PLACEMENT OF GRANITE CURB.

NOTES:

1. RAILING POST SHALL BE SET VERTICAL. RAILS SHALL FOLLOW THE GRADE OF THE ROADWAY.
2. RAILS SHALL BE CONTINUOUS OVER TWO OR MORE POSTS. EXPANSION SPLICES SHALL BE PLACED IN ANY PANEL WHERE EXPANSION JOINTS OCCUR.
3. ALL STRUCTURAL TUBING SHALL CONFORM TO THE REQUIREMENTS OF ASTM A500, GRADE B.
4. ALL BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 325.
5. ALL STRUCTURAL SHAPES, PLATES AND BARS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M 270 GRADE 36 (ASTM A709 GRADE 36).

		RECOMMENDED: <i>[Signature]</i> DEPUTY CHIEF ENGINEER
DATE	APPR.	APPROVED: <i>[Signature]</i>
REVISED		
ISSUED:	REFERENCE	CHIEF TRANSPORTATION ENGINEER

HISTORIC BRIDGE RAIL

d. DISTRICT OF COLUMBIA  
DEPARTMENT OF TRANSPORTATION

DWG. NO. 709.03

**APPENDIX B. HISTORIC BRIDGES REMOVED FROM SERVICE UNDER  
INDIANA'S PROGRAMMATIC AGREEMENT**

**Table B.1 – Historic bridges removed from service**

<b>NBI #</b>	<b>County</b>	<b>Structural Type</b>	<b>Railing Type</b>
0300003	Bartholomew	Metal Pony Truss	Metal 10
0300121	Bartholomew	Metal Pony Truss	Metal 10
0300024	Bartholomew	Metal Thru Truss	Metal 6
0400004	Benton	Reinforced Concrete Girder and Beam	Galvanized Beam
0600011	Boone	Metal Pony Truss	Metal 7
0600052	Boone	Reinforced Concrete Girder and Beam	Bush-Hammered Panel
0700031	Brown	Metal Pony Truss	None
0800129	Carroll	Reinforced Concrete Slab	None
1300067	Crawford	Metal Pony Truss	Galvanized Beam
1300008	Crawford	Metal Pony Truss	Metal 10
2800014	Greene	Metal Pony Truss	Metal 6
2800204	Greene	Timber Other	Timber 2
3600125	Jackson	Metal Pony Truss	None
3600103	Jackson	Metal Thru Truss	Metal 10
4000008	Jennings	Metal Pony Truss	Metal 6
4000015	Jennings	Reinforced Concrete Slab	None
4200147	Knox	Timber Other	Timber 2
4700122	Lawrence	Concrete Arch	Concrete 6
4700052	Lawrence	Metal Pony Truss	Metal 6
4700053	Lawrence	Metal Pony Truss	Metal 6
4700042	Lawrence	Metal Pony Truss	Metal 7
4800077	Madison	Metal Pony Truss	Metal 10
4900390	Marion	Prestressed Concrete Box Beam	Galvanized Beam
4900209	Marion	Reinforced Concrete Slab	Bush-Hammered Panel
5100061	Martin	Metal Pony Truss	Metal 10
5100006	Martin	Metal Pony Truss	Metal 10

**Table B.1 Continued**

5100040	Martin	Metal Pony Truss	Metal 10
5500125	Morgan	Concrete Arch	Bush-Hammered Panel
5500142	Morgan	Metal Pony Truss	Metal 10
5500024	Morgan	Reinforced Concrete Girder and Beam	Bush-Hammered Panel
5600093	Newton	Metal Thru Truss	Galvanized Beam
5900024	Orange	Steel Beam	Concrete 15
6300057	Pike	Metal Thru Truss	Metal 10
6500238	Posey	Metal Pony Truss	Metal 6
6500150	Posey	Metal Thru Truss	Metal 6
6700173	Putnam	Metal Pony Truss	Metal 10
6800181	Randolph	Metal Pony Truss	Metal 6
6900053	Ripley	Stone Arch	Stone 3
7300013	Shelby	Metal Thru Truss	Galvanized Beam
7400168	Spencer	Concrete Arch	Concrete 15
8000051	Tipton	Reinforced Concrete Girder and Beam	Concrete 21
8000009	Tipton	Reinforced Concrete Slab	Bush-Hammered Panel
8400113	Vigo	Metal Pony Truss	Metal 4
8800038	Washington	Metal Pony Truss	Galvanized Beam
8800040	Washington	Reinforced Concrete Slab	Concrete 2
9000058	Wells	Metal Pony Truss	Metal 6
5940	White	Concrete Arch	Concrete 6



### **APPENDIX C. PHOTOS OF HISTORIC BRIDGE RAILINGS**

Photos of all railing types observed on historic bridges in Indiana are provided. Each photo is accompanied by the name of the railing and the number of in-service bridges on which it appears.



**Concrete 1 (Bush-Hammered Panel) (74 bridges)**



**Concrete 2 (46 bridges)**



**Concrete 3 (2 bridges)**



**Concrete 4 (2 bridges)**



**Concrete 5 (1 bridge)**



**Concrete 6 (39 bridges)**



**Concrete 7 (12 bridges)**



**Concrete 8 (1 bridge)**





**Concrete 9 (1 bridge)**



**Concrete 10 (2 bridges)**



**Concrete 11 (1 bridge)**



**Concrete 12 (2 bridges)**



**Concrete 13 (1 bridge)**



**Concrete 14 (F-type) (14 bridges)**



**Concrete 15 (24 bridges)**



**Concrete 16 (2 bridges)**



**Concrete 17 (6 bridges)**





**Concrete 18 (6 bridges)**



**Concrete 19 (4 bridges)**



**Concrete 20 (1 bridge)**



**Concrete 21 (3 bridges)**



**Concrete 22 (1 bridge)**



**Concrete 23 (2 bridges)**





**Concrete 24 (2 bridges)**



**Concrete 25 (1 bridge)**



**Concrete 26 (1 bridge)**



**Metal 1 (15 bridges)**



**Metal 2 (9 bridges)**



**Metal 3 (1 bridge)**



**Metal 4 (1 bridge)**



**Metal 5 (Galvanized Beam) (75 bridges)**



**Metal 6 (78 bridges)**





**Metal 7 (9 bridges)**



**Metal 8 (2 bridges)**



**Metal 9 (24 bridges)**



**Metal 10 (38 bridges)**



**Metal 11 (1 bridge)**



**Metal 12 (6 bridges)**





**Metal 13 (1 bridge)**



**Metal 14 (7 bridges)**



**Metal and Concrete 1 (8 bridges)**



**Metal and Concrete 2 (2 bridges)**



**Metal and Concrete 3 (1 bridge)**



**Metal and Concrete 4 (F-type w/ Handrail) (1 bridge)**



**Pedestrian 1 (1 bridge)**



**Pedestrian 2 (1 bridge)**



**Pedestrian 3 (1 bridge)**





**Pedestrian 4 (1 bridge)**



**Pedestrian 5 (1 bridge)**



**Pedestrian 6 (2 bridges)**



**Pedestrian 7 (1 bridge)**



**Pedestrian 8 (1 bridge)**



**Stone 1 (1 bridge)**



**Stone 2 (10 bridges)**



**Stone 3 (13 bridges)**




**Stone 4 (1 bridge)**





**Stone 5 (3 bridges)**



**Stone 6 (1 bridge)**



**Timber 1 (47 bridges)**



**Timber 2 (6 bridges)**




**Timber 3 (2 bridges)**




**No Railing (35 bridges)**

**APPENDIX D. SIMULATED HISTORIC RAILING RENDERINGS**

**Concrete 1 (Bush-Hammered Panel)**




Parent Railing: TxDOT T221




Modified Railing



## Concrete 2




Parent Railing: TxDOT T221




Modified Railing



### Concrete 3




Parent Railing: TxDOT T221




Modified Railing

### Concrete 4




Parent Railing: TxDOT T221




Modified Railing

### Concrete 5




Parent Railing: TxDOT T221



Modified Railing


Concrete 6




Nearly Exact Approximation: INDOT TX



### Concrete 7




Parent Railing: ODOT Concrete Beam and Post




Modified Railing


### Concrete 8



Parent Railing: ODOT Concrete Beam and Post




Modified Railing (Option 1)




Modified Railing (Option 2 – Symmetric)


### Concrete 9



Parent Railing: ODOT Concrete Beam and Post




Modified Railing (Option 1)




Modified Railing (Option 2 – Symmetric)



### Concrete 10




Parent Railing: ODOT Concrete Beam and Post




Modified Railing



### Concrete 11




Parent Railing: ODOT Concrete Beam and Post




Modified Railing

### Concrete 12




Parent Railing: ODOT Concrete Beam and Post




Modified Railing

### Concrete 13




Parent Railing: ODOT Concrete Beam and Post



Modified Railing




**Concrete 15**




Nearly Exact Approximation: TxDOT T221

### Concrete 16




Parent Railing: TXDOT T221




Modified Railing

### Concrete 17




Parent Railing: TXDOT T221




Modified Railing



### Concrete 18




Parent Railing: TXDOT T221




Modified Railing

### Concrete 19




Parent Railing: INDOT FC




Modified Railing



**Concrete 20**




Parent Railing: TXDOT T221




Modified Railing

## Concrete 22




Parent Railing: ODOT Concrete Beam and Post




Modified Railing

### Concrete 23




Parent Railing: TXDOT T221



Modified Railing



**Concrete 25**




Parent Railing: TXDOT T221



Modified Railing


**Concrete 26**




Parent Railing: TXDOT T221



Modified Railing


**Metal 1**

Nearly Exact Approximation: ODOT Three-Tube Curb-Mounted Railing

**Metal 2**


Nearly Exact Approximation: ODOT Two-Tube Curb-Mounted Railing



**Metal 3**

Nearly Exact Approximation: ODOT Two-Tube Curb-Mounted Railing

### Metal 4




Approximation: CALTRANS Concrete Barrier Type 90 (Option 1)




Approximation: ODOT Two-Tube Curb-Mounted Railing (Option 2)


### Metal 6



Parent Railing: ODOT Two-Tube Curb-Mounted Railing




Modified Railing (Option 1 – Green)



Modified Railing (Option 2 – Blue; this is only a color variation)




### Metal 9




Nearly Exact Approximation: ODOT Two-Tube Curb-Mounted Railing


### Metal 14



Parent Railing: ODOT Two-Tube Curb-Mounted Railing




Modified Railing (Option 1 – Green)



Modified Railing (Option 2 – Blue; this is only a color variation)

### Pedestrian 1



Concept Railing: TXDOT PR3




Modified Railing



## Pedestrian 2



Concept Railing: TXDOT PR3



Modified Railing

### Pedestrian 3



Concept Railing: TXDOT PR3



Modified Railing

**Pedestrian 4**




Concept Railing: TXDOT PR3




Modified Railing



### Pedestrian 5



Concept Railing: ODOT Pedestrian Rail




Modified Railing

### Pedestrian 6




Concept Railing: TXDOT PR3




Modified Railing

### Pedestrian 7




Concept Railing: ODOT Pedestrian Rail



Modified Railing



**Stone 1**




Parent Railing: TXDOT T221




Modified Railing

**Stone 2**




Parent Railing: TXDOT T221




Modified Railing

**Stone 3**




Parent Railing: TXDOT T221




Modified Railing

**Stone 4**




Parent Railing: TXDOT T221




Modified Railing




### Stone 6



Parent Railing: ODOT Concrete Beam and Post




Modified Parent Railing (Option 1)



Modified Parent Railing (Option 2 – Symmetric)

**APPENDIX E. SIMULATED HISTORIC RAILING DRAWINGS**





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 1 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

23 OCTOBER 2014

DRAWING 1 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 1 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

23 OCTOBER 2014


DRAWING 1 OF 35

SHEET 2 OF 2

SCALE: 3/4" = 1'-0"



Between Panels



At Panel

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 2 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

24 OCTOBER 2014

DRAWING 2 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 2 PROFILE



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


24 OCTOBER 2014

DRAWING 2 OF 35

SHEET 2 OF 2

SCALE: 3/4" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 3 PROFILE



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


24 OCTOBER 2014

DRAWING 3 OF 35

SHEET 2 OF 2

SCALE: 3/4" = 1'-0"





Between Posts

At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 4 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

24 OCTOBER 2014

DRAWING 4 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 4 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

24 OCTOBER 2014


DRAWING 4 OF 35

SHEET 2 OF 2

SCALE: 1/2" = 1'-0"



Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 5 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

26 OCTOBER 2014

DRAWING 5 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 5 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

26 OCTOBER 2014

DRAWING 5 OF 35

SHEET 2 OF 2

SCALE: 1/2" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 7 CROSS-SECTIONS





STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

26 OCTOBER 2014

DRAWING 6 OF 35

SHEET 1 OF 3

SCALE: 3/4" = 1'-0"




1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING


### CONCRETE 7 SUNK-IN PANEL DETAIL




SCALE: 3" = 1'-0"







Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 8 CROSS-SECTIONS (1)




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014


DRAWING 7 OF 35

SHEET 1 OF 3

SCALE: 3/4" = 1'-0"



Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE POST  
AND BEAM RAILING

PURDUE UNIVERSITY

## CONCRETE 8 CROSS-SECTIONS (2)




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014


DRAWING 7 OF 35

SHEET 2 OF 3


SCALE: 3/4" = 1'-0"



Trapezoidal Block



Triangular Block



Profile

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

**CONCRETE 8  
PROFILE & BLOCKS**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


27 OCTOBER 2014

DRAWING 7 OF 35

SHEET 3 OF 3

SCALE: 3/4" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 9 CROSS-SECTIONS (2)



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


28 OCTOBER 2014

DRAWING 8 OF 35


SHEET 2 OF 4

SCALE: 3/4" = 1'-0"





Cross-Section



Profile

**NOTES**

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

**CONCRETE 9  
SUNK-IN PANEL DETAIL**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

31 OCTOBER 2014


DRAWING 8 OF 35

SHEET 3 OF 4


SCALE: 3" = 1'-0"



Ovular Block



Rectangular Block



Profile

#### NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 9 PROFILE & BLOCKS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

28 OCTOBER 2014


DRAWING 8 OF 35

SHEET 4 OF 4

SCALE: 3/4" = 1'-0"



Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 10 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

28 OCTOBER 2014


DRAWING 9 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



Profile



Block: Profile

Block: Side

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 10 PROFILE & BLOCK




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


28 OCTOBER 2014

DRAWING 9 OF 35


SHEET 2 OF 2

SCALE: 3/4" = 1'-0"






Profile



Arch Insert: Profile



Arch Insert: Side

**NOTES**

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

**CONCRETE 11  
PROFILE & ARCH INSERT**



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


28 OCTOBER 2014

DRAWING 10 OF 35


SHEET 2 OF 2

SCALE: 3/4" = 1'-0"





Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 12 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014

DRAWING 11 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



# NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 12 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


30 OCTOBER 2014

DRAWING 11 OF 35


SHEET 2 OF 2

SCALE: 3/4" = 1'-0"





Cross-Section



Profile

### NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 13 SUNK-IN PANEL DETAIL




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

31 OCTOBER 2014

DRAWING 12 OF 35

SHEET 2 OF 3

SCALE: 3" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 13 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

28 OCTOBER 2014

DRAWING 12 OF 35

SHEET 3 OF 3

SCALE: 3/4" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 16 CROSS-SECTIONS



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


30 OCTOBER 2014

DRAWING 13 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 16 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014


DRAWING 13 OF 35

SHEET 2 OF 2

SCALE: 1/2" = 1'-0"



Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

**CONCRETE 17**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


30 OCTOBER 2014

DRAWING 14 OF 35

SHEET 1 OF 1

SCALE: 3/4" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE INDOT FC RAILING

PURDUE UNIVERSITY

## CONCRETE 19 CROSS-SECTION





STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014

DRAWING 16 OF 35

SHEET 1 OF 2

SCALE: 1" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE INDOT FC RAILING

PURDUE UNIVERSITY

## CONCRETE 19 PROFILES




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014


DRAWING 16 OF 35

SHEET 2 OF 2

SCALE: 1/2" = 1'-0"



Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

**CONCRETE 20**



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


30 OCTOBER 2014

DRAWING 17 OF 35

SHEET 1 OF 1

SCALE: 3/4" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 22 CROSS-SECTION




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014

DRAWING 18 OF 35

SHEET 1 OF 2

SCALE: 1" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

## CONCRETE 22 PROFILES




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014


DRAWING 18 OF 35

SHEET 2 OF 2

SCALE: 1/2" = 1'-0"



Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 23 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014


DRAWING 19 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



End Panel



Middle Panel

**NOTES**

1. THIS DRAWING SUPPLEMENTS THE STANDARD DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

**CONCRETE 23  
PROFILES**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014


DRAWING 19 OF 35

SHEET 2 OF 2

SCALE: 1/2" = 1'-0"



Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 25 CROSS-SECTIONS




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014

DRAWING 20 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING

PURDUE UNIVERSITY

## CONCRETE 25 PROFILE



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


30 OCTOBER 2014

DRAWING 20 OF 35


SHEET 2 OF 2

SCALE: 1/2" = 1'-0"





Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING


PURDUE UNIVERSITY

**CONCRETE 26**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

30 OCTOBER 2014  
DRAWING 21 OF 35  
SHEET 1 OF 1  
SCALE: 1/2" = 1'-0"



Backside Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT TWO-TUBE  
RAILING
2. PAINT METAL ATTACHMENTS TO MATCH BRIDGE

PURDUE UNIVERSITY

**METAL 6**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014


DRAWING 22 OF 35

SHEET 1 OF 1

SCALE: 1/2" = 1'-0"



Backside Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT TWO-TUBE  
RAILING
2. PAINT METAL ATTACHMENTS TO MATCH BRIDGE

PURDUE UNIVERSITY

**METAL 14**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


27 OCTOBER 2014

DRAWING 23 OF 35

SHEET 1 OF 1

SCALE: 1/2" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT PR3 RAILING
2. OPENING DIMENSIONS ARE CLEAR SPACINGS

PURDUE UNIVERSITY

## PEDESTRIAN 2 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

28 OCTOBER 2014

DRAWING 25 OF 35

SHEET 1 OF 1

SCALE: 1/2" = 1'-0"



## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT PR3 RAILING
2. OPENING DIMENSIONS ARE CLEAR SPACINGS

PURDUE UNIVERSITY

## PEDESTRIAN 3 PROFILE



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


28 OCTOBER 2014

DRAWING 26 OF 35

SHEET 1 OF 1

SCALE: 1/2" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT PR3 RAILING
2. OPENING DIMENSIONS ARE CLEAR SPACINGS

PURDUE UNIVERSITY

## PEDESTRIAN 4 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


28 OCTOBER 2014

DRAWING 27 OF 35

SHEET 1 OF 1

SCALE: 1/2" = 1'-0"





## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT PR3 RAILING
2. OPENING DIMENSIONS ARE CLEAR SPACINGS

PURDUE UNIVERSITY

## PEDESTRIAN 6 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


28 OCTOBER 2014


DRAWING 29 OF 35

SHEET 1 OF 1


SCALE: 1/2" = 1'-0"







Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD DETAIL DRAWING(S) OF THE TxDOT T221 RAILING
2. 1-3/8" FORM LINER RELIEF (CUSTOM ROCK "NEW ENGLAND DRYSTACK")

PURDUE UNIVERSITY

**STONE 2**




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014


DRAWING 32 OF 35

SHEET 1 OF 1

SCALE: 3/4" = 1'-0"



Profile



Cross-Section

NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD DETAIL DRAWING(S) OF THE TxDOT T221 RAILING
2. 1-3/8" FORM LINER RELIEF (CUSTOM ROCK "NEW ENGLAND DRYSTACK")

PURDUE UNIVERSITY

**STONE 3**



STRATEGIES FOR THE REPLACEMENT OF HISTORIC BRIDGE GUARDRAILS


27 OCTOBER 2014

DRAWING 33 OF 35


SHEET 1 OF 1

SCALE: 3/4" = 1'-0"







Cross-Section



Block: Top



Block: Elevation 1



Block: Elevation 2

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD DETAIL DRAWING(S) OF THE TxDOT T221 RAILING
2. 1-1/2" FORM LINER RELIEF (CUSTOM ROCK "TOLLWAY ASHLAR")

PURDUE UNIVERSITY

## STONE 4 CROSS-SECTION




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014

DRAWING 34 OF 35

SHEET 1 OF 2

SCALE: 3/4" = 1'-0"



#### NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE TxDOT T221 RAILING
2. 1-1/2" FORM LINER RELIEF (CUSTOM ROCK  
"TOLLWAY ASHLAR")

PURDUE UNIVERSITY

## STONE 4 PROFILE




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS


27 OCTOBER 2014

DRAWING 34 OF 35


SHEET 2 OF 2

SCALE: 3/8" = 1'-0"





Between Posts



At Post

## NOTES

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE POST  
AND BEAM RAILING

PURDUE UNIVERSITY

## STONE 6 CROSS-SECTIONS (2)




STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014


DRAWING 35 OF 35

SHEET 2 OF 3


SCALE: 3/4" = 1'-0"



Triangular Block



Trapezoidal Block



Profile

**NOTES**

1. THIS DRAWING SUPPLEMENTS THE STANDARD  
DETAIL DRAWING(S) OF THE ODOT CONCRETE BEAM  
AND POST RAILING

PURDUE UNIVERSITY

**STONE 6  
PROFILE & INSERTS**



STRATEGIES FOR THE  
REPLACEMENT OF HISTORIC  
BRIDGE GUARDRAILS

27 OCTOBER 2014

DRAWING 35 OF 35

SHEET 3 OF 3

SCALE: 3/4" = 1'-0"

## VITA

## **VITA**

Adam Joseph Clauss was born in Terre Haute, Indiana on June 26, 1990. He is the eldest son of Mark and Barbara Clauss and has one younger brother, Aaron Clauss. After graduating in the top 5% of his class from Terre Haute North Vigo High School in 2009, he entered Purdue University in West Lafayette, Indiana. In May 2013, Adam graduated with a Bachelor of Science in Civil Engineering with highest distinction. Adam received a Chappelle Fellowship to continue his studies at Purdue and began his graduate program in August 2013. During his graduate studies, he worked as a graduate research assistant working towards advancing the practice of rehabilitation of historic bridge guardrails.